NOTES:

1. EMERGENCY POWER BACK UP FOR SMOKE EXTRACTION SYSTEM

	NORMAL MODE	FIRE MODE	FAILURE IN NORMAL POWER MODE
AFA SYSTEM	STANDBY	ACTIVITED	FED BY EMERGENCY POWER
SMOKE EXTRACTION SYSTEM	STANDBY	ACTIVITED	FED BY EMERGENCY POWER

EMERGENCY SUPPLY SHALL BE PROVIDED TO THE MOTORIZED FIRE AND SMOKE DAMPER (MFSD) AS WELL AS SMOKE EXTRACTION FANS/MAKEUP AIR FANS.

2. FAIL SAFE OPERATION OF MOTORIZED FIRE AND SMOKE DAMPER (MFSD) SHALL ENSURE TO MAINTAIN THE FREE PASSAGE OF SMOKE
3. THE SMOKE EXTRACTION SYSTEM IS DESIGNED WITH ASSUMPTION OF ACTUATION FROM ITS SERVING ZONING
4. ALL MOTORIZED FIRE AND SMOKE DAMPER(MFSD) SHALL COMPLY WITH THE PERFORMANCE TEST STIPULATED IN UL555S.
5. ALL MOTORIZED FIRE AND SMOKE DAMPER(MFSD) CONTROL PANELS SHALL BE INSTALLED IN FS CONTROL ROOM OR PROTECTED AREAS OR ENCLOSED WITH FIRE RATED ENCLOSURE.
6. UPON ACTUATION OF ANY SMOKE EXTRACTION SYSTEMS, MOTORIZED FIRE AND SMOKE DAMPERS (MFSD) OF ASSOCIATED GENERAL EXHAUST LOUVER SHALL BE CLOSED.
7. MAKEUP AIR FAN (MAF) SHALL BE INTERLOCKED WITH SMOKE EXTRACTION FAN (SEF) ACCORDING TO THE FOLLOWING SCENARIOS:
   A. FOR EACH SYSTEM, IF ANY ONE SEF SERVING THE COMPARTMENT IS "ON", THE CORRESPONDING MAKEUP AIR FAN (MAF) SHALL BE STARTED UP.
   B. FOR EACH SYSTEM, IF ANY ONE SEF SERVING THE COMPARTMENT IS "OFF" OR "FAILURE", THE CORRESPONDING MAF SHALL BE SHUT DOWN AND CANNOT BE STARTED UP.
   C. FOR EACH SYSTEM, IF ANY ONE MAF SERVING THE COMPARTMENT IS "OFF" OR :FAILURE:, THE SEF(S) WILL BE CONTINUED TO OPERATE.

MODE TABLE FOR SMOKE EXTRACTION SYSTEM OF B2 LOADING AND UNLOADING AREA (SYSTEM 1)

MODE		FAN								MFSD								FIRE SHUTTER STATUS
		SMOKE EXTRACTION SYSTEM				NORMAL VENTILATION SYSTEM				SMOKE EXTRACTION SYSTEM								FIRE SHUTTER
		SEF-B2-01	SEF-B2-02	MAF-B2-01	MAF-B1-03	EAF-B2-03	EAF-B2-04	FAF-B2-03	FAF-B2-04	MFSD-SEF-B2-01	MFSD-SEF-B2-02	MFSD-SEF-B2-03	MFSD-SEF-B2-04	MFSD-MAF-B2-01	MFSD-MAF-B2-02	MFSD-MAF-B1-05	MFSD-MAF-B1-06	B2F-FS-01
NORMAL MODE		OFF	OFF	OFF	OFF	ON	ON	ON	ON	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	OPEN
FIRE MODE	ALL EQUIPMENT NORMAL OPERATION	ON	ON	ON	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF SEF-B2-01	OFF	ON	OFF	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF SEF-B2-02	ON	OFF	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF BOTH SEF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF MAF-B2-01	ON	ON	OFF	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF MAF-B1-03	ON	ON	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF BOTH MAF	ON	ON	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
NO POWER MODE		OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	–

MODE		NORMAL VENTILATION SYSTEM							FIRE SHUTTER STATUS
		MFSD							FIRE SHUTTER
		MFSD-EAF-B2-01	MFSD-EAF-B2-02	MFSD-EAF-B2-03	MFSD-EAF-B2-04	MFSD-FAF-B2-01	MFSD-FAF-B2-02	MFSD-FAF-B1-03	B2F-FS-01
NORMAL MODE		OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
FIRE MODE	ALL EQUIPMENT NORMAL OPERATION	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B2-01	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B2-02	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH SEF	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B2-01	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B1-03	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH MAF	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
NO POWER MODE		OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	–

MODE TABLE FOR SMOKE EXTRACTION SYSTEM OF B1 LOADING AND UNLOADING AREA (SYSTEM 2)

MODE		FAN								MFSD								FIRE SHUTTER STATUS
		SMOKE EXTRACTION SYSTEM				NORMAL VENTILATION SYSTEM				SMOKE EXTRACTION SYSTEM								FIRE SHUTTER
		SEF-B1-03	SEF-B1-04	MAF-B1-04	MAF-B1-05	FAF-B1-04	FAF-B2-03	EAF-B1-10	EAF-B1-11	MFSD-SEF-B1-05	MFSD-SEF-B1-06	MFSD-SEF-B1-07	MFSD-SEF-B1-08	MFSD-MAF-B1-09	MFSD-MAF-B1-10	MFSD-MAF-B1-07	MFSD-MAF-B1-08	B1F-FS-01
NORMAL MODE		OFF	OFF	OFF	OFF	ON	ON	ON	ON	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	OPEN
FIRE MODE	ALL EQUIPMENT NORMAL OPERATION	ON	ON	ON	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF SEF-B1-03	OFF	ON	OFF	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF SEF-B1-04	ON	OFF	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF BOTH SEF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF MAF-B1-04	ON	ON	OFF	ON	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF MAF-B1-05	ON	ON	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
	FAILURE OF BOTH MAF	ON	ON	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE
NO POWER MODE		OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	–

MODE		NORMAL VENTILATION SYSTEM							FIRE SHUTTER STATUS
		MFSD							FIRE SHUTTER
		MFSD-EAF-B1-01	MFSD-EAF-B1-02	MFSD-EAF-B1-03	MFSD-EAF-B1-04	MFSD-FAF-B1-01	MFSD-FAF-B1-02	MFSD-FAF-B1-03	B1F-FS-01
NORMAL MODE		OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
FIRE MODE	ALL EQUIPMENT NORMAL OPERATION	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B1-03	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B1-04	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH SEF	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B1-04	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B1-05	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH MAF	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
NO POWER MODE		OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	–

MODE TABLE FOR SMOKE EXTRACTION SYSTEM OF B1 RETAIL AREA (SYSTEM 3)

MODE		FAN									MFSD										
		SMOKE EXTRACTION SYSTEM				NORMAL VENTILATION SYSTEM					SMOKE EXTRACTION SYSTEM								NORMAL VENTILATION SYSTEM		
		SEF-B1-01	SEF-B1-02	MAF-B1-01	MAF-B1-02	EAF-B3-01	EAF-B3-02	EAF-B2-02	EAF-B1-02	PAU-B1-02	MFSD-SEF-B1-01	MFSD-SEF-B1-02	MFSD-SEF-B1-03	MFSD-SEF-B1-04	MFSD-MAF-B1-01	MFSD-MAF-B1-02	MFSD-MAF-B1-03	MFSD-MAF-B1-04	MFSD-EAF-B1-05	MFSD-EAF-B1-06	MFSD-EAF-B1-07	MFSD-EAF-B1-08	MFSD-PAU-B1-01
NORMAL MODE		OFF	OFF	OFF	OFF	ON	ON	ON	ON	ON	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE	OPEN	OPEN	OPEN	OPEN	OPEN
FIRE MODE	ALL EQUIPMENT NORMAL OPERATION	ON	ON	ON	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B1-01	OFF	ON	OFF	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF SEF-B1-02	ON	OFF	ON	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH SEF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B1-01	ON	ON	OFF	ON	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF MAF-B1-02	ON	ON	ON	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
	FAILURE OF BOTH MAF	ON	ON	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE
NO POWER MODE		OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OFF	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSE	CLOSE	CLOSE	CLOSE	CLOSE

FIRE SERVICE INSTALLATION PLANS AS CERTIFIED BY THE AUTHORIZED PERSON AND FIRE SERVICE INSTALLATION CONTRACTOR / CONSULTANT
Date 08 SEP 2026
Signed (FUNG Kam-wah)
for Director of Fire Services

LOO Kwan Wai
(RPE No.: RP0260258)

NO.	DATE	REVISIONS	DRAFTED	CHECKED	DESIGNED	REVIEWED
A	09/2025	FSD SECOND SUBMISSION	HYH	WWC	HYH	TKL
0	05/2025	FSD FIRST SUBMISSION	HYH	WWC	HYH	TKL

CLIENT:

NATION STAR DEVELOPMENT LIMITED
75/F, 8 Finance Street,
Central, Hong Kong

PROJECT ARCHITECT & AUTHORIZED PERSON:

RONALD LU & PARTNERS
呂元祥建築師事務所
33rd Floor, Wu Chung house, 213 Queen's Road East,
Wanchai, Hong Kong

STRUCTURAL/GEOTECHNICAL

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

BUILDING SERVICES ENGINEER:

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

QUANTITY SURVEYOR:

ARCADIS
17/F, Two Harbour Square, 180 Wai Yip Street,
Kwun Tong, Kowloon
Hong Kong

FIRE SERVICES CONTRACTOR:

開創工程有限公司
GRAND CREATIVE ENGINEERS LIMITED

PROJECT:
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON
INLAND LOT NO. 11279
(URA PROJECT KC-009)

TITLE:
SMOKE EXTRACTION SYSTEM-MODE TABLE

(5)

DATE: 06/2026		SCALE: NTS@A0	
DRAFTED: HYH	CHECKED: WWC	DESIGNED: HYH	REVIEWED: TKL
JOB NO. 2503373A	DRAWING NO. 2503373A/SES/102		REV. NO. A