GENERAL NOTES:

1. MANUAL OVERRIDE SWITCHES PANEL SHALL BE PROVIDED AT THE G/F FIRE CONTROL ROOM ~~TO ALLOW SWITCHING OFF THE FANS FOR ALL THE MECHANICAL VENTILATING SYSTEMS SERVING THE COMPARTMENTS IN THE EVENT OF AN EMERGENCY IN ACCORDANCE WITH FSD'S STANDARDS AND REQUIREMENTS.~~
2. ALL VRV A/C INDOOR UNITS AND SPLIT TYPE A/C INDOOR UNITS (SIU) UNITS FLOW RATE DO NOT EXCEED 1000L/S AND SERVING SINGLE COMPARTMENT.
3. NO FIRE ENGINEERING REPORT RELATED TO VENTILATION/AIR CONDITIONING CONTROL SYSTEM.
4. METHOD 'C' VAC TRIPPING METHOD IS ADOPTED FOR THIS VAC CONTROL SYSTEM.

ABBREVIATIONS

A.P.	ACCESS PANEL
E.A.	EXHAUST AIR
EAD	EXHAUST AIR DUCT
EAG	EXHAUST AIR GRILLE
EAL	EXHAUST AIR LOUVRE
EAF	EXHAUST AIR FAN
FAL	FRESH AIR LOUVRE
F.A.	FRESH AIR
TAL	TRANSFER AIR LOUVRE
T.A.	TRANSFER AIR
FAD	FRESH AIR DUCT
FAG	FRESH AIR GRILLE
FAF	FRESH AIR FAN
F/A	FROM ABOVE
F/B	FROM BELOW
F.D.	FIRE DAMPER
H/L	HIGH LEVEL
HP	HEAT PUMP
L/L	LOW LEVEL
T/A	TO ABOVE
T/B	TO BELOW
VCD	VOLUME CONTROL DAMPER
W.P.	WEATHER PROOF
W.P.L.	WEATHER PROOF LOUVRE
E.T.L.	ELECTRO THERMAL FUSIBLE LINK
O.D.	OUT DOOR
BOA	BUILDING OPEN AIR
EOA	EXTERNAL OPEN AIR
PAU	PRIMARY AIR UNIT
MVAC	MECHANICAL VENTILATION AND AIR CONDITIONING
N/R	Not Required For Fire Trip

F.S. Notes :

'Method – C' the vent / AC Control will be used.

LEGENDS:

	FLEXIBLE CONNECTION IN DUCT
W X H	DUCT
	VOLUME CONTROL DAMPER
M	MOTOR POWERED VOLUME CONTROL DAMPER
	RECTANGULAR TRANSITION
	RECTANGULAR TO CIRCULAR TRANSITION
	PROPELLER / CELING FAN
	IN-LINE CENTRIFUGAL / CENTRIFUGAL FAN
	JET FAN (600L/S)
FD	FIRE DAMPER
MSFD	MOTORISED SMOKE AND FIRE DAMPER
A / B C / (D)	A= EQUIPMENT ABBREVIATION EAF – EXHAUST AIR FAN FAF – FRESH AIR FAN PAU – PRIMARY AIR UNIT B= LEVEL (FLOOR) C= UNIT NUMBER D= FLOW RATE (L/s)
	VAC MANUAL OVERRIDE SWITCH PANEL & VAC PANEL
	F.S. CONTROL PANEL
	F.R.P. ENCLOSURE
SIL	ACOUSTIC SILENCER
BOG	BIO-OXYGEN GENERATOR
	FRESH AIR LOUVER/EXHAUST AIR LOUVER
S	SMOKE DETECTOR

VIU–X.X (Flow Rate L/S) / VIU–X.X — VIU–XX(W) VRV WALL MOUNT TYPE INDOOR; VIU–XX(D) VRV DUCT TYPE INDOOR

FAP–X.X(Flow Rate L/S) / FAP–X.X — FAP–XX FRESH AIR PRIMARY VRV DUCT TYPE INDOOR

SCHEDULE OF VRV (PODIUM)

Designation For VAC	No.	Flow Rate (L/s)
VIU–03(D)	87	293
VIU–04(D)	4	158
VIU–05(D)	13	150
FAP–01	7	300
FAP–02	1	467
FAP–03	3	583

SCHEDULE OF FAN COIL UNIT(FCU)

Designation For VAC	No.	Flow Rate (L/s)
FCU–04	5	186
FCU–06	4	297
FCU–08	30	372

SCHEDULE OF A/C INDOOR UNIT(SIU)

Designation For VAC	No.	Flow Rate (L/s)
SIU–01(D)	9	572

ALL ABOVE A/C INDOOR UNIT ARE FLOW RATE LESS THAN 1000L/S AND SERVE SINGLE FIRE COMPARTMENT IN ABOVE TABLES


FCU–X.X. (Flow Rate L/s) / FCU–X.X. FCU–XX FAN COIL UNIT

SIU–X.X. (Flow Rate L/s) / SIU–X.X. SIU–XX SPLIT TYPE INDOOR UNIT

ABBREVIATIONS

M.A.	MAKE UP AIR
K.E.	KITCHEN EXHAUST
S.E.	SMOKE EXTRACTION
S.E.F.	SMOKE EXTRACTION FAN (REFER TO SEPARATE SUBMISSION)
M.A.F.	MAKE UP AIR FAN (REFER TO SEPARATE SUBMISSION)

DETAIL OF MANUAL OVERRIDE PANEL




NOTE:

1. SHUT DOWN OF VENTILATION FANS SHALL BE DUE TO:
   (a) F.S SIGNAL FROM DRY CONTACT OR
   (b) OPERATION OF THE MANUAL OVERRIDE SWITCH OF THE MANUAL OVERRIDE PANEL IN THE FIRE SERVICES CONTROL ROOM AND ALL SUCH CONTROL ACTIONS SHALL BE FAIL–SAFE.
2. MINIMUM SIZE OF CONTROL WIRINGS WILL BE 1.5mm².
3. ALL CABLE SIZES WILL COMPLY WITH THE LATEST EDITION OF THE IEE REGULATIONS, CLP'S SUPPLY RULES AS WELL AS THE ELECTRICAL (WIRING) REGULATIONS.
4. COMMON FIRE ALARM SIGNAL IN DRY CONTACT WILL BE PROVIDED IN THE FIRE SERVICES CONTROL CENTRE.

VAC MANUAL OVERRIDE SWITCH PANEL (FOR REFERENCE ONLY)

G/F F.S. CONTROL ROOM PART PLAN ~~1:100~~ N.T.S
REF. TO DRAWING NO. : P42424/FSD/VAC/215



REMARKS:
N/R – NOT REQUIRED FOR FIRE TRIP
C – REQUIRED FOR FIRE TRIP

THE FOLLOWING MECHANICAL VENTILATING SYSTEMS SHALL BE EXEMPTED FROM THESE REQUIREMENTS: (EXTRACTED FROM FSD COP 5.27)

(a) ANY MECHANICAL VENTILATING SYSTEM FORMING PART OF THE FIRE SERVICE INSTALLATIONS AND INSTALLED SOLELY FOR FIRE PROTECTION OR FIRE FIGHTING PURPOSES, I.E. STAIRCASE PRESSURIZATION SYSTEM AND SMOKE EXTRACTION SYSTEM.
(b) INDIVIDUAL, SELF–CONTAINED OR SPLIT–TYPE, DIRECT EXPANSION ROOM COOLING UNITS NOT CONNECTED TO DUCTWORK SYSTEMS.
(c) MINOR MECHANICAL VENTILATION SYSTEM WHICH COMPLY WITH ALL OF THE FOLLOWING CRITERIA:
   (1) ALL AIR DISTRIBUTING DUCTWORK SYSTEMS ARE CONTAINED WITHIN THE SAME COMPARTMENT.
   (2) THE AIR FLOW RATE HANDLED BY EACH AIR DISTRIBUTION DUCTWORK SYSTEM DOES NOT EXCEED 1000 LITERS PER SECOND.
(d) MECHANICAL VENTILATION SYSTEM WHERE ALL AIR IS SUPPLIED AT LOW LEVEL I.E. FUME CUPBOARD VENTILATION, KITCHEN VENTILATION, SYSTEM HANDLING TOXIC GASES/EXPLOSIVE, ETC.
(e) MECHANICAL VENTILATING SYSTEMS WHERE ALL AIR IS SUPPLIED AT LOW LEVEL AND / OR EXTRACTED (NOT RECIRCULATED) AT HIGH LEVEL.
(f) INDIVIDUAL PLANT ROOMS, AND INDIVIDUAL TOILETS WHICH ARE MECHANICALLY VENTILATED DIRECTLY (I.E. VENTILATING SYSTEM NOT SERVING OTHER AREAS) TO OUTSIDE.

EXCEPT RESIDENTIAL TOWERS AS PER FSD'S CODES OF PRACTICE 4.23, VENTILATION/AIR CONDITIONING CONTROL SYSTEMS SHALL BE PROVIDED AND SHALL COMPLY WITH CURRENT FSD'S CODES OF PRACTICE 2012 EDITION.

DRAWING LIST

Drawing No.	Rev.	Drawing Title	SCALE
P42424/FSD/VAC/001	A	VAC LEGENDS, ABBREVIATION, GENERAL NOTES	N.T.S.
P42424/FSD/VAC/002	A	VAC EQUIPMENT SCHEDULE	N.T.S.
P42424/FSD/VAC/101	A	AIR SIDE SCHEMATIC DIAGRAM – PODIUM (B3/F TO 1/F) (SHEET 1 OF 2)	N.T.S.
P42424/FSD/VAC/102	A	AIR SIDE SCHEMATIC DIAGRAM – PODIUM (B3/F TO 1/F) (SHEET 2 OF 2)	N.T.S.
P42424/FSD/VAC/103	A	MECHANICAL VENTILATION SCHEMATIC DIAGRAM – PODIUM (B3/F TO 3/F) (SHEET 1 OF 2)	N.T.S.
P42424/FSD/VAC/104	A	MECHANICAL VENTILATION SCHEMATIC DIAGRAM – PODIUM (B3/F TO 3/F) (SHEET 2 OF 2)	N.T.S.
P42424/FSD/VAC/105	A	AIR SIDE SCHEMATIC DIAGRAM – PODIUM (2/F)	N.T.S.
P42424/FSD/VAC/201	0	VAC LAYOUT PLAN AT B3/F (SHEET 1 OF 3)	1:100@A1
P42424/FSD/VAC/202	0	VAC LAYOUT PLAN AT B3/F (SHEET 2 OF 3)	1:100@A1
P42424/FSD/VAC/203	0	VAC LAYOUT PLAN AT B3/F (SHEET 3 OF 3)	1:100@A1
P42424/FSD/VAC/204	A	VAC LAYOUT PLAN AT B2/F (SHEET 1 OF 4)	1:100@A1
P42424/FSD/VAC/205	A	VAC LAYOUT PLAN AT B2/F (SHEET 2 OF 4)	1:100@A1
P42424/FSD/VAC/206	A	VAC LAYOUT PLAN AT B2/F (SHEET 3 OF 4)	1:100@A1
P42424/FSD/VAC/207	A	VAC LAYOUT PLAN AT B2/F (SHEET 4 OF 4)	1:100@A1
P42424/FSD/VAC/208	A	VAC LAYOUT PLAN AT B1/F (SHEET 1 OF 4)	1:100@A1
P42424/FSD/VAC/209	A	VAC LAYOUT PLAN AT B1/F (SHEET 2 OF 4)	1:100@A1
P42424/FSD/VAC/210	A	VAC LAYOUT PLAN AT B1/F (SHEET 3 OF 4)	1:100@A1
P42424/FSD/VAC/211	A	VAC LAYOUT PLAN AT B1/F (SHEET 4 OF 4)	1:100@A1
P42424/FSD/VAC/212	A	VAC LAYOUT PLAN AT G/F (SHEET 1 OF 4)	1:100@A1
P42424/FSD/VAC/213	A	VAC LAYOUT PLAN AT G/F (SHEET 2 OF 4)	1:100@A1
P42424/FSD/VAC/214	A	VAC LAYOUT PLAN AT G/F (SHEET 3 OF 4)	1:100@A1
P42424/FSD/VAC/215	A	VAC LAYOUT PLAN AT G/F (SHEET 4 OF 4)	1:100@A1
P42424/FSD/VAC/216	A	VAC LAYOUT PLAN AT 1/F (SHEET 1 OF 4)	1:100@A1
P42424/FSD/VAC/217	A	VAC LAYOUT PLAN AT 1/F (SHEET 2 OF 4)	1:100@A1
P42424/FSD/VAC/218	A	VAC LAYOUT PLAN AT 1/F (SHEET 3 OF 4)	1:100@A1
P42424/FSD/VAC/219	A	VAC LAYOUT PLAN AT 1/F (SHEET 4 OF 4)	1:100@A1
P42424/FSD/VAC/220	A	VAC LAYOUT PLAN AT 2/F (SHEET 1 OF 4)	1:100@A1
P42424/FSD/VAC/221	A	VAC LAYOUT PLAN AT 2/F (SHEET 2 OF 4)	1:100@A1
P42424/FSD/VAC/222	A	VAC LAYOUT PLAN AT 2/F (SHEET 3 OF 4)	1:100@A1
P42424/FSD/VAC/223	A	VAC LAYOUT PLAN AT 2/F (SHEET 4 OF 4)	1:100@A1
P42424/FSD/VAC/224	A	VAC LAYOUT PLAN AT 3/F	1:100@A1

BLOCK PLAN SCALE : 1:500

LEGEND REFER TO P42424–FSD–VAC–001

REV.	DESCRIPTION	DATE
A	SECOND SUBMISSION	17/06/2026
0	FIRST SUBMISSION	18/11/2025

CLIENT:

NATION STAR DEVELOPMENT LIMITED
75/F, 8 Finance Street,
Central, Hong Kong

ARCHITECT:

RONALD LU & PARTNERS 呂元祥建築師事務所
33rd Floor, Wu Chung house, 213 Queen's Road East, Wanchai, Hong Kong

STRUCTURAL GEOTECHNICAL:

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

M&E SERVICES CONSULTANT:

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

MAIN CONTRACTOR

中國海外房屋工程有限公司 CHINA OVERSEAS BUILDING CONSTRUCTION LIMITED
139, China Overseas Building, Hennessy Road
Wan Chai, Hong Kong

MVAC SUB–CONTRACTOR:

Sun Yu Chau Engineering Company Limited
12/F, Kwan Centre, No. 9 Hung To Road
Kwun Tong, Kowloon, Hong Kong
TEL : (852)2343 9355 FAX : (852)2797 0387

FIRE SERVICES CONTRACTOR:

開創工程有限公司 GRAND CREATIVE ENGINEERS LIMITED

PROJECT:

PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON
INLAND LOT NO. 11279
(URA PROJECT KC–009)

TITLE:

VAC LEGENDS, ABBREVIATION, GENERAL NOTES

JOB NO.	SCALE	DATE	DRAWING BY
P42424	N.T.S. @A1	17/06/2026	OY
P42424/FSD/VAC/001		CHECKED BY	APPROVED BY
		KM	WW
REV.	0 A		