VENTIALTION/AIR CONDITIONING FAN SCHEDULE(PODIUM)

Floor	Item	Designation For VAC	No. of Fan	Served Location	Equipment Location	~~Type of Fan~~	Flow Rate (L/s)	Method of Fire Trip	Exemption Reason	Drawing NO.Layout P42424/FSD/VAC/ XXX
B3/F	1	EAF-B3-01	1	RESIDENTIAL CARPARK(B3/F)	RESIDENTIAL CARPARK(B3/F)	Plug Fan	6200	C		201
	2	EAF-B3-02	1	RESIDENTIAL CARPARK(B3/F)	RESIDENTIAL CARPARK(B3/F)	Plug Fan	6200	C		201
	3	FAF-B3-01	1	RESIDENTIAL CARPARK(B3/F)	RESIDENTIAL CARPARK(B3/F)	Plug Fan	4960	C		202
	4	FAF-B3-02	1	RESIDENTIAL CARPARK(B3/F)	RESIDENTIAL CARPARK(B3/F)	Plug Fan	4960	C		201
	5	JF-B3-01 TO JF-B3-16	16	RESIDENTIAL CARPARK(B3/F)	RESIDENTIAL CARPARK(B3/F)	Jet Fan	600	N/R	F.S COP 5.27(c)	201,202,203
B2/F	6	EAF-B2-01	1	PUBLIC VEHICLE PARK (PVP)	FAN ROOM(FOR PVP)	In-line Centrifugal	5450	C		205
	7	EAF-B2-02	1	PUBLIC VEHICLE PARK (PVP)	FAN ROOM(FOR PVP)	In-line Centrifugal	5450	C		204
	8	EAF-B2-03	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	In-line Centrifugal	4250	C		207
	9	EAF-B2-04	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	In-line Centrifugal	4250	C		207
	10	EAF-B2-05	1	SPRINKLER WATER TANK & PUMP RM.(FOR TOWER 3)	SPRINKLER WATER TANK & PUMP RM.(FOR TOWER 3)	In-line Centrifugal	800	C		206
	11	EAF-B2-06	1	POTABLE WATER TANK& PUMP ROOM(FOR COMMERCIAL)	POTABLE WATER TANK& PUMP ROOM(FOR COMMERCIAL)	In-line Centrifugal	600	C		206
	12	EAF-B2-09	1	F.S.PUMP RM.(FOR TOWER 5)	F.S.PUMP RM.(FOR TOWER 5)	In-line Centrifugal	400	C		206
	13	EAF-B2-10	1	POTABLE & FLUSHING WATER TANK &UPFEED PUMP RM.(FOR TOWER 2)	POTABLE & FLUSHING WATER TANK &UPFEED PUMP RM.(FOR TOWER 2)	In-line Centrifugal	700	C		205
	14	EAF-B2-13	1	POTABLE WATER TANK & UPEED PUMP RM.(FOR TOWER1)	POTABLE WATER TANK & UPEED PUMP RM.(FOR TOWER1)	In-line Centrifugal	800	C		207
	15	EAF-B2-15	1	F.S. & SPRINKLER WATER TANK AND PUMP ROOM(FOR TOWER1)	F.S. & SPRINKLER WATER TANK AND PUMP ROOM(FOR TOWER1)	In-line Centrifugal	700	C		207
	16	EAF-B2-16	1	WATER METER RM. (FOR COMMERCIAL & RESIDENTIAL)	WATER METER RM. (FOR COMMERCIAL & RESIDENTIAL)	In-line Centrifugal	200	C		207
	17	FAF-B2-01	1	PUBLIC VEHICLE PARK (PVP)	PUBLIC VEHICLE PARK (PVP)	Plug Fan	4360	C		204
	18	FAF-B2-02	1	~~PUBLIC VEHICLE PARK (PVP)~~&COMMERCIAL CARPARK(B1/F) AND B2/F	~~PUBLIC VEHICLE PARK (PVP)~~ COMMERCIAL CARPARK (B2/F)	Plug Fan	5880	C		204
	19	FAF-B2-03	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	Plug Fan	3400	C		207
	20	FAF-B2-04	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	Plug Fan	3400	C		207
	21	JF-B2-01 TO JF-B2-27	27	PUBLIC VEHICLE PARK (PVP)(B2/F)	PUBLIC VEHICLE PARK (PVP)(B2/F)	Jet Fan	600	N/R	F.S COP 5.27(c)	204,205,206,207
	22	SEF-B2-01*	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	Plug Fan	7800	INDICATE THE SMOKE EXTRACTION SYSTEM REFER TO SEPARATE SUBMISSION		
	23	SEF-B2-02*	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	Plug Fan	7800			
	24	MAF-B2-01*	1	COMMERCIAL CARPARK(B2/F)	COMMERCIAL CARPARK(B2/F)	Plug Fan	6240			
B1/F	25	EAF-B1-01	1	COMMERCIAL CARPARK(B1/F) & ~~PUBLIC VEHICLE PARK (PVP)(B2/F)~~ COMMERCIAL CARPARK (B2/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	7350	C		211
	26	EAF-B1-02	1	MASTER METER RM (FOR COMMERRCIAL & RESIDENTIAL)	MASTER METER RM (FOR COMMERRCIAL & RESIDENTIAL)	In-line Centrifugal	300	C		208
	27	EAF-B1-03	1	SPRINKLER & F.S. WATER TANK & PUMP RM.(FOR PODIUM AND TOWER 2)/SPRINKLER WATER TANK & PUMP RM.(FOR TOWER 5)/ FLUSHING WATER TANK & UPFEED PUMP RM.1(FOR TOWER 3)/ POTABLE WATER TANK & UPFEED PUMP RM.1(FOR TOWER 3)	FAN ROOM (FOR COMMERCIAL)	Centrifugal	4700	C		210
	28	EAF-B1-04	1	FLUSHING WATER METER RM./POTABLE & FLUSHING WATER TANK&UPFEED PUMP ROOM(FOR TOWER 5)/POTABLE & FLUSHING WATER TANK&PUMP ROOM(FOR R.R.F.)/F.S.WATER TANK & PUMP ROOM(FOR TOWER 5) Upfeed	FAN ROOM (FOR COMMERCIAL)	Centrifugal	2500	C		210
	29	EAF-B1-05	1	ACCESSIBLE TOILET /F.LAV	ACCESSIBLE TOILET	In-line Centrifugal	405	C		211
	30	EAF-B1-06	1	~~ACCESSIBLE TOILET~~ /M.LAV	ACCESSIBLE TOILET	In-line Centrifugal	300	C		211
	31	EAF-B1-08	1	WATER METER ROOM	WATER METER ROOM	In-line Centrifugal	100	C		211
	32	EAF-B1-09	1	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 1 & CHAMBER 2	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 2	Plug Fan	4300	C		211
	33	EAF-B1-10	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	4200	C		211
	34	EAF-B1-11	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	4200	C		211
	35	FAF-B1-01	1	~~COMMERCIAL CARPARK(B1/F)~~ & PUBLIC VEHICLE PARK (PVP)(B2/F)	FAN ROOM (FOR COMMERCIAL)	Plug Fan	4360	C		210
	36	FAF-B1-02	1	CORRIDOR	FAN ROOM (FOR COMMERCIAL)	Plug Fan	3600	C		210
	37	FAF-B1-03	1	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 1 & CHAMBER 2	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 2	Plug Fan	4300	C		211
	38	FAF-B1-04	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	3360	C		211
	39	VES-B1-01	1	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 1	REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 1	Vehicle Exhaust	400	C		211
	40	JF-B1-01 TO JF-B1-02	2	COMMERCIAL CARPARK (B1/F)	COMMERCIAL CARPARK (B1/F)	Jet Fan	600	N/R	F.S COP 5.27(c)	211
	41	PAU-B1-01	1	SHOP B02,B03,B04,B05	P.A.U. ROOM(FOR COMMERCIAL)	Primary Air unit	6400	C		208
	42	PAU-B1-02	1	SHOP B01 & SHOPPING ARCADE	P.A.U. ROOM	Primary Air unit	4400	C		208
	43	EAF-B1-TYP01	3	SHOP B02 & SHOP B03 & SHOP B04	SHOP B02 & SHOP B03 & SHOP B04	In-line Centrifugal	30	N/R	F.S COP 5.27(c)	208
	44	SEF-B1-03*	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	7800	INDICATE THE SMOKE EXTRACTION SYSTEM REFER TO SEPARATE SUBMISSION		
	45	SEF-B1-04*	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	7800			
	46	MAF-B1-04*	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	6240			
	47	MAF-B1-05*	1	COMMERCIAL CARPARK(B1/F)	COMMERCIAL CARPARK(B1/F)	Plug Fan	6240			
G/F	48	EAF-GF-TYP01	15	SHOP G02,G03,G04,G05,G06,G08,G09,~~G11~~,G12,G17,G19,G21,G22,G23,G24	SHOP G02,G03,G04,G05,G06,G08,G09,~~G11~~,G12,G17,G19,G21,G22,G23,G24	In-line Centrifugal	30	N/R	F.S COP 5.27(c)	212,213,214,215
	49	~~EAF-GF-TYP01 TYP02~~	5	SHOP G01,G13,G14,G15,G16, G11	SHOP G01,G13,G14,G15,G16, G11	In-line Centrifugal	30	C		215
	50	EAF-GF-01	1	SPRINKLER CONTROL VALVE RM.	SPRINKLER CONTROL VALVE RM.	In-line Centrifugal	200	C		215
	51	EAF-GF-02	1	SHOP G23 ACCESSIBLE TOILET	SHOP G23 ACCESSIBLE TOILET	In-line Centrifugal	47	N/R	F.S COP 5.27(c)	214
	52	EAF-GF-03	1	SHOP G24 ACCESSIBLE TOILET	SHOP G24 ACCESSIBLE TOILET	In-line Centrifugal	50	N/R	F.S COP 5.27(c)	214
	53	EAF-GF-04	1	LIFT L13 & LIFT L14	CORRIDOR	In-line Centrifugal	220	C		212
	54	PAU-GF-01	1	SHOP G23 & SHOP G24 & SHOP 120	PAU ROOM(FOR RETAIL)	Primary Air unit	5700	C		213
1/F	55	EAF-1F-01	1	SHOP 120 ACCESSIBLE TOILET	CORRIDOR	In-line Centrifugal	52	~~N/R~~ C	~~F.S COP 5.27(c)~~	217
	56	EAF-1F-02	1	SHOP 120 LAV	CORRIDOR	In-line Centrifugal	34	~~N/R~~ C	~~F.S COP 5.27(c)~~	218
	57	EAF-1F-03	1	LIFT L16	CORRIDOR	In-line Centrifugal	130	C		218
	58	EAF-1F-06	1	ACCESSIBLE TOILET	ACCESSIBLE TOILET	In-line Centrifugal	70	C		219
	59	EAF-1F-TYP01	7	SHOP 101,103,104,108,118,120	SHOP 101,103,104,108,118,120	In-line Centrifugal	30	C		216,217,218,219
	60	EAF-1F-07	1	F.LAV & M.LAV & BABYCARE ROOM	M.LAV	In-line Centrifugal	950	C		219
	61	EAF-1F-08	1	MANAGEMENT OFFICE ~~& CHANGING ROOM~~ (For Retail)	MANAGEMENT OFFICE (For Retail)	In-line Centrifugal	200	~~C~~ N/R	F.S COP 5.27(c)	219
	62	EAF-1F-09	1	F.LAV & M.LAV	M.LAV	In-line Centrifugal	135	C		216
	63	PAU-1F-01	1	SHOP 115,116,117,118,119 & SHOPPING ARCADE	P.A.U. ROOM	Primary Air unit	3340	C		217
	64	PAU-1F-02	1	SHOP 102,103,104,105,106,107,108,109,110 & SHOPPING ARCADE	P.A.U. ROOM	Primary Air unit	7450	C		219
	65	PAU-1F-03	1	SHOP 101,111,112,113,114 & SHOPPING ARCADE	P.A.U. ROOM	Primary Air unit	3360	C		219
2/F	66	EAF-2F-01	1	SPA 2	~~CORRIDOR~~ SPA 2	In-line Centrifugal	100	~~N/R~~ C	~~F.S COP 5.27(c)~~	223
	67	EAF-2F-02	1	F.CHANGING ROOM	F.CHANGING ROOM	In-line Centrifugal	600	N/R	F.S COP 5.27(c)	223
	68	EAF-2F-03	1	M.CHANGING ROOM	M.CHANGING ROOM	In-line Centrifugal	530	N/R	F.S COP 5.27(c)	220
	69	EAF-2F-04	1	LAV.1	JANIOR RM.	In-line Centrifugal	60	~~N/R~~ C	~~F.S COP 5.27(c)~~	220
	70	EAF-2F-05	1	LAV.2	LAV.2	In-line Centrifugal	25	~~N/R~~ C	~~F.S COP 5.27(c)~~	220
	71	EAF-2F-06	1	FILTRATION PLANT ROOM(FOR SWIMMING POOL)	FILTRATION PLANT ROOM(FOR SWIMMING POOL)	In-line Centrifugal	500	N/R	F.S COP 5.27(f)	221
	72	EAF-2F-07	1	LIFT L17 & LIFT L18	STORE ROOM	In-line Centrifugal	140	C		223
	73	EAF-2F-08	1	LIFT L19	CORRIDOR	Propeller	50	C		220
	74	EAF-2F-09	1	LIFT L15	CORRIDOR	Propeller	100	C		223
	75	EAF-2F-10	1	FUNCTION ROOM 1 SINK1	FUNCTION ROOM 1	In-line Centrifugal	70	C		220
	76	EAF-2F-11	1	LAV.3	FUNCTION ROOM 2	In-line Centrifugal	40	C		220
	77	EAF-2F-12	1	ACCESSIBLE TOILET	ACCESSIBLE TOILET	In-line Centrifugal	60	C		223
	78	EAF-2F-13	1	FUNCTION ROOM 2 SINK1 AND SINK 2	FUNCTION ROOM 2	In-line Centrifugal	70	C		220
	79	EAF-2F-14	1	CARETAKERS QUARTERS AND BATH	~~LAV~~ CARETAKERS QUARTERS & LAV	In-line Centrifugal	80	C		221
	80	EAF-2F-15	1	ACC TOILET	ACC TOILET	In-line Centrifugal	50	C		222
	81	EAF-2F-16	1	MANAGEMENT OFFICE (RESIDENTIAL)	MANAGEMENT OFFICE (RESIDENTIAL)	In-line Centrifugal	30	C		222
	82	EAF-2F-17	1	OWNER'S COMMITTEE OFFICE	OWNER'S COMMITTEE OFFICE	In-line Centrifugal	30	N/R	F.S COP 5.27(c)	222
	83	EAF-2F-18	1	FAMILY TOILET	~~COVERED LANDSCAPE~~ FAMILY TOILET	In-line Centrifugal	65	C		222
	84	EAF-2F-19	1	CHILDREN PLAY ROOM LAV./F.LAV./M.LAV.	CHILDREN PLAY ROOM	In-line Centrifugal	480	N/R	F.S COP 5.27(c)	223
	84	EAF-2F-20	1	SPA 1	~~CORRIDOR~~ SPA 1	In-line Centrifugal	100	C		223
	84	EAF-2F-21	1	COVERED LANDSCAPE AREA	COVERED LANDSCAPE AREA	In-line Centrifugal	100	N/R	F.S COP 5.27(c)	220
	84	EAF-2F-22	1	COVERED LANDSCAPE AREA	COVERED LANDSCAPE AREA	In-line Centrifugal	100	N/R	F.S COP 5.27(c)	220
	85	FAF-2F-01	1	FUNCTION ROOM 1	FUNCTION ROOM 1	In-line Centrifugal	300	N/R	F.S COP 5.27(c)	220

~~TOTAL NOS. OF FAN (PODIUM) : B3/F (20 NOS.), B2/F (42 NOS.),B1/F (22 NOS.),G/F (25 NOS.),1/F (17 NOS.), 2/F (23 NOS.)~~
~~TOTAL NOS. OF FAN (PODIUM) REQUIRED FOR FIRE TRIP: 75 NOS.~~
~~TOTAL NOS. OF FAN FOR SMOKE EXTRACTION SYSTEM REFER TO SEPARATE SUBMISSION : B2/F (3 NOS.),B1/F (4 NOS.)~~

Not for this VAC submission

Not for this VAC Submission

LEGEND REFER TO P42424-FSD-VAC-001

* SMOKE EXTRACTION SYSTEM REFER TO SEPARATE SUBMISSION

REV.	DESCRIPTION	DATE
A	SECOND SUBMISSION	17/06/2026
0	FIRST SUBMISSION	18/11/2025

CLIENT:

NATION STAR DEVELOPMENT LIMITED
75/F, 8 Finance Street,
Central, Hong Kong

ARCHITECT:

RONALD LU & PARTNERS 呂元祥建築師事務所
33rd Floor, Wu Chung house, 213 Queen's Road East, Wanchai, Hong Kong

STRUCTURAL GEOTECHNICAL:

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

M&E SERVICES CONSULTANT:

wsp
7/F, One Kowloon
1 Wang Yuen Street
Kowloon Bay, Hong Kong

MAIN CONTRACTOR

中國海外基屋工程有限公司 CHINA OVERSEAS BUILDING CONSTRUCTION LIMITED
139, China Overseas Building, Hennessy Road
Wan Chai, Hong Kong

MVAC SUB-CONTRACTOR:

Sun Yu Chau Engineering Company Limited
22/F, Kwan Grace, No. 9 Hing To Road
Kwun Tong, Kowloon, Hong Kong
TEL.: (852)2345 9555 FAX: (852)2797 0387

FIRE SERVICES CONTRACTOR:

開創工程有限公司 GRAND CREATIVE ENGINEERS LIMITED

FIRE SERVICE INSTALLATION PLANS AS CERTIFIED BY THE AUTHORIZED PERSON AND FIRE SERVICE INSTALLATION CONTRACTOR / CONSULTANT
Date 10 SEP 2026
Signed (WU Wai-kei)
for Director of Fire Services

PROJECT:

PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON
INLAND LOT NO. 11279
(URA PROJECT KC-009)

TITLE:

VAC EQUIPMENT SCHEDULE

JOB NO.	SCALE	DATE	DRAWING BY
P42424	N.T.S. @A1	17/06/2026	CY
P42424/FSD/VAC/002		CHECKED BY	APPROVED BY
		KM	WW

REV. 0 A