GENERAL NOTES

1. UNLESS OTHERWISE STATED, BRANCH PIPE SIZE SHALL BE AS FOLLOWS:

WASTE BRANCH FOR EACH WASH BASIN	ø32mm
WASTE BRANCH FOR EACH BATHTUB	ø40mm
WASTE BRANCH FOR EACH SHOWER TRAY	ø50mm
WASTE BRANCH FOR EACH FLOOR DRAIN IN BATHROOM/ KITCHEN/ TOILET	ø50mm
WASTE BRANCH FOR EACH KITCHEN SINK	ø50mm
WASTE BRANCH FOR EACH WASHING MACHINE/ DISH WASHER	ø40mm
WASTE BRANCH FOR EACH VERTICAL GRATING IN BATHROOM/ KITCHEN	ø50mm
SOIL BRANCH FOR EACH WATER CLOSET	ø100mm
VENT BRANCH FOR EACH WATER CLOSET/ URINAL	ø50mm
SOIL BRANCH FOR EACH URINAL	ø50mm

2. SIZE OF TRAPS FOR FITMENTS SHALL BE THE SAME AS THE PIPE SIZE NOTED FOR FITMENTS.
3. WHETHER SHOWN ON THE DRAWINGS OR NOT, SUFFICIENT ACCESS SHALL BE PROVIDED BY MEANS OF CLEANING EYES OR OTHER APPROVED METHOD TO ENABLE ALL DRAINAGE PIPES TO BE CLEARED OF ANY OBSTRUCTION. SUCH ACCESS POINTS SHALL BE SITED SO AS TO ALLOW CLEARANCE FOR THE EASY ENTRY OF CLEANING ROD.
4. ALL BENDS IN SOIL PIPES AND WASTE PIPES SHALL HAVE AN OBTUSE ANGLE AND HAVE THE LARGEST PRACTICABLE RADIUS OF CURVATURE. THE BENDS SHALL NOT CHANGE IN ANY WAY OF THE SECTION OF THE PIPE AND A CLEANING EYE SHALL BE PROVIDED AT OR NEAR THE BEND.
5. EVERY ANTI-SYPHONAGE PIPE SHALL BE CONNECTED WITH THE TRAP IF THE CONNECTION FOR THE ANTI-SYPHONAGE PIPES IS AN INTEGRAL PART OF THE TRAP OR SHALL BE CONNECTED WITH THE BRANCH SOIL PIPE OR BRANCH WASTE PIPE, AT A POINT NOT MORE THAN 300mm FROM THE TRAP OUTLET.
6. WHERE THE WASTE PIPE FROM A WASTE FITMENT IS CONNECTED TO A SOIL PIPE, THE TRAP PROVIDED FOR THE WASTE FITMENT SHALL HAVE A WATER SEAL OF 80mm AND BE VENTILATED BY MEANS OF ANTI-SYPHONAGE PIPE.
7. RE-SEALING TRAPS WITH A WATER SEAL OF 80mm SHALL BE USED WHERE ANTI-SYPHONAGE PIPES HAVE NOT BEEN PROVIDED IN ITEM 6 ABOVE AND WHERE MORE THAN ONE TRAP OF WASTE FITMENT IS CONNECTED WITH ONE WASTE PIPE.
8. ALL SOIL VENTILATING PIPES AND WASTE VENTILATING PIPES ARE TO BE TERMINATED ABOVE ROOF LEVEL EITHER 1100mm WITH WIRE BALLOONS OR 3000mm FROM FINISH FLOOR LEVEL & ANY OPENING WITH FLAT GRATINGS AS SPECIFIED IN RELEVANT DRAWINGS.
9. HORIZONTAL VENT PIPES SHALL BE SLIGHTLY INCLINED UPWARD CONNECTED TO VENT STACK.
10. ALL LEVELS ARE REFERRED TO PRINCIPAL DATUM IN METRE.
11. EVERY DRAIN OR SEWER SHALL BE LAID WITH A MINIMUM FALL AS FOLLOWS OR AS INDICATED ON DRAWINGS:

    ø100mm AND BELOW AT 1 TO 40 — ø225mm AT 1 TO 100 — ø400mm AT 1 TO 200
    ø150mm AT 1 TO 70 — ø250mm AT 1 TO 125
    ø200mm AT 1 TO 90 — ø300mm AT 1 TO 150

12. FACES OF EVERY MANHOLE SHALL BE RENDERED WITH CEMENT MORTAR SO AS TO PROVIDE A SMOOTH AND IMPERVIOUS SURFACE.
13. EVERY DRAINAGE CHANNEL IN A MANHOLE SHALL NOT BE LESS THAN HALF ROUND OF GLAZED EARTHEN WARE OR CEMENT RENDERED AND SHALL HAVE A DIAMETER NOT LESS THAN THAT OF THE LARGEST DRAINAGE INLET INTO AND NOT MORE THAN THAT OF THE OUTLET FROM THE MANHOLE.
14. EVERY DRAINAGE INLET TO A MANHOLE SHALL DISCHARGE INTO THE DRAINAGE CHANNEL THEREIN WITH PROPERLY MADE BENDS CONSTRUCTED WITH THE BENCHING OF THE MANHOLE.
15. EVERY MANHOLE SHALL BE FITTED AT A LEVEL FLUSHED WITH GROUND LEVEL WITH A CAST IRON AIRTIGHT COVER OF ADEQUATE STRENGTH AND APPROVED DESIGN. EVERY MANHOLE OR GREASE TRAP INSIDE OR UNDER A BUILDING SHALL BE FITTED WITH A DOUBLE SEALED CAST IRON AIRTIGHT COVER.
16. ALL MANHOLE FRAMES AND COVERS SHALL BE OF AN APPROVED DESIGN CONFORMING TO THE FOLLOWING REQUIREMENTS, UNLESS OTHERWISE INDICATED:

    A. OPEN AREA – MEDIUM DUTY TYPE DOUBLE SEAL (HEAVY DUTY TYPE DOUBLE SEAL FOR CARPARK AREA AND DRIVEWAY)
    B. INSIDE BUILDING – LIGHT DUTY TYPE DOUBLE SEAL (HEAVY DUTY TYPE DOUBLE SEAL FOR CARPARK AND PLANT ROOM AREA)

17. ALL DRAINS ARE TO BE LAID ON A CONCRETE (1:3:6) BED NOT LESS THAN 100mm THICK AND AT LEAST 150mm WIDER THAN THE PIPE BORE AND HAUNCHED UP BOTH SIDES WITH CONCRETE TO MEET THE PIPE BARREL TANGENTIALLY.
18. ALL INVERT LEVELS SHOWN ON MANHOLES ARE THE INVERT LEVEL OF THE MAIN CHANNELS IN THE CENTRE OF MANHOLES.
19. ALL UNDERGROUND DRAINS SHALL BE DULY TESTED PRIOR TO THE BACKFILLING OF TRENCHES AND SHOULD BE COUPLED WITH PNAC11 AND PNAP APP-58
20. SUPPORT SHALL BE PROVIDED FOR ALL UNDERGROUND DRAINAGE AT AN INTERVAL OF NOT MORE THAN 1500mm.
21. POSITION OF MANHOLES AND PITS SHALL BE COORDINATED WITH OTHER TRADES/SERVICES. EXACT POSITION AND SET-OUT TO BE DETERMINATED ON SITE.
22. ALL PIPES PASSING THROUGH FIRE PROTECTED AREAS SHALL BE ENCLOSED BY FIRE RATED PROOFING MATERIALS OF APPROPRIATE FIRE RATING REQUIRED BY HKFSD.
23. ALL CHANNEL GRATING SHOULD BE AN APPROVED DESIGN CONFORMING TO THE FOLLOWING REQUIREMENTS, UNLESS OTHERWISE INDICATED:

    A. NON-CARPARK AREA AND NON-VEHICULAR ACCESS AREA – MEDIUM DUTY TYPE
    B. CARPARK AREA AND VEHICULAR ACCESS AREA – HEAVY DUTY TYPE

24. UNLESS OTHERWISE STATED, ALL SURFACE CHANNEL SHOULD BE LAID ON 1:100 FALL. MIN. FALL TOWARDS TO OUTLET
25. UNLESS OTHERWISE STATED, ALL SURFACE CHANNEL WITH GRATING SHOULD BE LAID ON 1:100 FALL. MIN. FALL TOWARDS TO OUTLET
26. UNLESS OTHERWISE STATED, ALL CANOPY SHOULD BE LAID ON 1:75 FALL.
27. UNLESS OTHERWISE STATED, ALL ROOF AND FLAT ROOF SHOULD BE LAID ON 1:80 FALL.
28. ALL CONDENSATE DRAIN SHOULD BE DISCHARGED/CONNECTED TO STORM WATER SYSTEM.
29. UNLESS OTHERWISE STATED, ALL PLANTER DRAIN SHOULD BE DISCHARGED/CONNECTED TO STORM WATER SYSTEM.
30. UNLESS OTHERWISE STATED, ALL VENT PIPE WHICH IS SERVED FOR SEALED TRAPPED GULLY, SUMP PUMP PIT OR PETROL INTERCEPTOR SHOULD BE SIZED AS ø100mm.
31. WHETHER SHOWN ON THE DRAWINGS OR NOT, ALL DIMENSIONS FOR PETROL INTERCEPTOR SHOULD REFER TO APPROVED STANDARD.
32. ALL PIPES PASSING THROUGH FIRE COMPARTMENT SHOULD BE COMPLIED WITH CODE OF PRACTICE FOR FIRE SAFETY IN BUILDINGS 2011.
33. NO DRAINAGE PIPING SHALL BE EMBEDDED IN STRUCTURAL ELEMENT AS STATED ON PNAP APP105.
34. ALL C.I. PIPES SHOULD BE COMPLIED WITH PNAP APP133.
35. MAINTENANCE ACCESS TO COMMON DRAINAGE PIPES LOCATED WITHIN THE LIGHTWELL, PIPE WELL AND/OR RE-ENTRANT WILL BE PROVIDED AND SUCH ACCESS WILL BE PROVIDED VIA AREAS TO BE DESIGNATED AS COMMON PARTS.
36. DRAINAGE WORKS OUTSIDE LOT BOUNDARY ARE FOR BD REFERENCE ONLY.
37. ALL SHOWER DRAIN, BATH DRAIN AND FLOOR DRAIN AT SUNKEN SHALL BE TOP ACCESS TYPE
38. CLEANING EYE OF DIA.50 MM SHALL BE PROVIDED, UNLESS OTHERWISE STATED IN DRAWINGS
39. THE BURIED SERVICES PLACED IN A SLOPE SHOULD BE COMPLIED WITH PNAP APP–76
40. STRUCTURAL DESIGN & CALCULATION OF MANHOLE, SUMP PIT, PETROL INTERCEPTOR ETC. TO BE SUBMITTED SEPARATELY.
41. EVERY RAIN WATER PIPE, WHICH DISCHARGE TO A CHANNEL SHALL DISCHARGE AT A HEIGHT NOT MORE THAN 150MM ABOVE THE LEVEL OF TOP OF THE GRATING BUT ABOVE THE LEVEL OF THE WATER IN THE TRAP
42. UNLESS OTHERWISE STATED, DROP PIPES SHALL BE PROVIDED IN MANHOLES FOR IN DRAINS WITH INVERT LEVEL MORE THAN 600MM HIGHER THAN THE INVERT LEVEL OF OUT DRAINS (DRAINS INCLUDE SURFACE WATER AND FOUL WATER DRAINS)
43. CROSS VENTILATION SHOULD BE PROVIDED TO THE DRAINAGE STACK VIA CONNECTIONS WITH A MAIN ANTI-SYPHONAGE PIPE SUCH CONNECTIONS SHOULD BE COMPLY WITH APP 164. A CONNECTION SHOULD BE PROVIDED AT A POINT BELOW THE LOWEST BRANCH DISCHARGE PIPE AND ABOVE THE BEND OF AN OFFSET OF THE DRAINAGE STACK.
44. NO DRAINAGE PIPE CONNECTION IS PERMITTED WITHIN A RESTRICTED ZONE AT EVERY OFFSET. THE RESTRICTED ZONE IS 1000MM ABOVE THE BEND AND WITHIN 2500MM AWAY FROM THE BEND HORIZONTALLY.
45. THE FOLLOWING PNAP AND REGULATIONS SHALL BE COMPLIED WITH :

    (i) APP13, 27, 58, 93, 99, 105, 112, 125 &164
    (ii) BUILDING SSFPD CHAPTER 123I

46. FRR ENCLOSURE SHALL BE PROVIDED IN REQUIRED STAIRCASE, PROTECTED LOBBY, PROTECTED CORRIDOR, PROTECTED EXIT AND FIREMAN LIFT LOBBY.

SYMBOL	ABBREVIATION	DESCRIPTION
	SWP	SOIL & WASTE PIPE / SOIL PIPE
	WP	WASTE PIPE
	RWP	RAIN WATER PIPE
	VP/ASP	VENT PIPE / ANTI-SYPHONAGE PIPE
	RP	REFILLING PIPE
	CDP	CONDENSATE DRAIN PIPE
R		EXISTING RAIN WATER PIPE
S		EXISTING SOIL & WASTE PIPE
		PERFORATED PIPE / SUB-SOIL PIPE
	RG	ROAD GULLY
	RWO	RAIN WATER OUTLET
	FD	FLOOR DRAIN WITH RESEALING PIPE
	TG/TFD/BD/TSD	TRAPPED GULLY / TOP ACCESS FLOOR DRAIN / BATH DRAIN / TOP ACCESS SHOWER DRAIN
	OTG	OPEN TRAPPED GULLY
	PD	PLANTER DRAIN
	PD W/ PIT	PLANTER DRAIN WITH PIT
	BIGT	BACK INLET GULLY TRAP
	VG	VERTICAL GRATING
	FAI	FRESH AIR INLET
	FMH / WMH	FOUL WATER MANHOLE/ WASTE WATER MANHOLE
	SMH	STORM WATER MANHOLE
	PI	PETROL INTERCEPTOR
	FTMH	FOUL WATER TERMINAL MANHOLE WITH DISCONNECTING TRAP
	RTMH	RAIN WATER TERMINAL MANHOLE WITH DISCONNECTING TRAP
		WIRE BALLOON/ VENT COWL W/ UVC STERILIZATION DEVICE
		RE-SEALING TRAP
		P-TRAP
		PVC ANTI-SYPHONAGE TRAP
		PVC ANTI-SYPHONAGE BOTTLE TRAP
	WC	FLOOR MOUNTED TYPE WATER CLOSET
	W.B.	WASH BASIN
	URL	URINAL
		KITCHEN / PANTRY SINK
		DISHED CHANNEL
		SURFACE CHANNEL WITH GRATING (GRATING BY OTHERS)
SD Shaped		SHOWER TRAY
		ø40 TEE OFF W/ BOTTOM TRAP TERMINATED AT 300mm AFFL W/450mm HEIGHT ø40 UPVC PIPE EXTENSION FOR WASHING MACHINE / DISH WASHER (TYP.)
		BATHTUB
	LMCP	LOCAL MOTOR CONTROL PANEL
	C.E.	CLEANING EYE
		REDUCER
		WEEP HOLE
UV		UV STERILIZATION DEVICE

SYMBOL	DESCRIPTION
	FRR ENCLOSURE
	50 DEPTH SUNKEN
	225 DEPTH SUNKEN
	300 DEPTH SUNKEN
	350 DEPTH SUNKEN
	400 DEPTH SUNKEN
	GATE VALVE
	NON-RETURN VALVE
	SUMP PIT WITH SUMP PUMP SETS

ABBREVIATION	DESCRIPTION
CI	CAST IRON
DI	DUCTILE IRON
GI	GALVANIZED STEEL
uPVC	UNPLASTICIZED POLYVINYL CHLORIDE
PVC	POLYVINYL CHLORIDE
CL.	COVER LEVEL
IL.	INVERT LEVEL
BL.	BOTTOM LEVEL
EJ	EXPANSION JOINT
DTIL.	DISCONNECTING TRAP INVERT LEVEL
AFFL.	ABOVE FINISHED FLOOR LEVEL
H/L	HIGH LEVEL
M/L	MIDDLE LEVEL
L/L	LOW LEVEL
H.W.L	HIGH WATER LEVEL
L.W.L.	LOW WATER LEVEL
O/F	OVERFLOW
C/W	COMPLETE WITH
F/A	FROM ABOVE
F/B	FROM BELOW
T/A	TO ABOVE
T/B	TO BELOW
U/G	UNDERGROUND
HKFSD	HONG KONG FIRE SERVICES DEPARTMENT
FRR	FIRE RESISTANCE RATING
S.S.	STAINLESS STEEL
NC	NORMAL CLOSE
NO	NORMAL OPEN
W.M.	WASHING MACHINE
DW	DISH WASHER
GH	GAS HEATER
L TO R	LEFT TO RIGHT
T TO B	TOP TO BOTTOM
R TO L	RIGHT TO LEFT
H/Z	HIGH ZONE
L/Z	LOW ZONE
W/	WITH
CPWP	CARPARK WASTE PIPE
VP(R)	VENT PIPE (RAINWATER)

DRAWINGS SCHEDULE

BDAWING NO.	REV.	TITLE	SCALE
2503373A–BD–001	G	DRAINAGE SYSTEM – GENERAL NOTES, LEGENDS, ABBREVIATION, DESCRIPTION, BLOCK PLAN DRAWINGS SCHEDULE AND PIPEWORK MATERIAL SCHEDULE	N.T.S.
2503373A–BD–101	F	FOUL WATER SCHEMATIC DIAGRAM FOR PODIUM (SHEET 1 OF 2)	N.T.S.
2503373A–BD–102	F	FOUL WATER SCHEMATIC DIAGRAM FOR PODIUM (SHEET 2 OF 2)	N.T.S.
2503373A–BD–103	D	FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 1	N.T.S.
2503373A–BD–104	D	FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 2	N.T.S.
2503373A–BD–105	D	FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 3	N.T.S.
2503373A–BD–106	D	FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 5	N.T.S.
2503373A–BD–201–1	E	DRAINAGE LAYOUT – BASEMENT 3 FLOOR (UNDERGROUND)	1:200
2503373A–BD–201–2	E	DRAINAGE LAYOUT – BASEMENT 3 FLOOR (HIGH LEVEL)	1:200
2503373A–BD–202	E	DRAINAGE LAYOUT – BASEMENT 2 FLOOR	1:200
2503373A–BD–203	E	DRAINAGE LAYOUT – BASEMENT 1 FLOOR	1:200
2503373A–BD–204	E	DRAINAGE LAYOUT – GROUND FLOOR	1:200
2503373A–BD–205	E	DRAINAGE LAYOUT – 1ST FLOOR	1:200
2503373A–BD–206	E	DRAINAGE LAYOUT – 2ND FLOOR	1:200
2503373A–BD–207	F	DRAINAGE LAYOUT – 3RD FLOOR	1:200
2503373A–BD–301	F	DRAINAGE LAYOUT – TOWER 1 & TOWER 2 3RD FLOOR	1:100
2503373A–BD–302	F	DRAINAGE LAYOUT – TOWER 1 & TOWER 2 5TH – 29TH FLOOR	1:100
2503373A–BD–302–1	E	DRAINAGE LAYOUT – TOWER 1 & TOWER 2 30TH FLOOR	1:100
2503373A–BD–303	E	DRAINAGE LAYOUT – TOWER 1 & TOWER 2 ROOF FLOOR	1:100
2503373A–BD–304	E	DRAINAGE LAYOUT – TOWER 1 & TOWER 2 UPPER ROOF FLOOR	1:100
2503373A–BD–305	F	DRAINAGE LAYOUT – TOWER 3 3RD – 30TH FLOOR	1:100
2503373A–BD–306	E	DRAINAGE LAYOUT – TOWER 3 ROOF & UPPER ROOF FLOOR	1:100
2503373A–BD–307	F	DRAINAGE LAYOUT – TOWER 5 3RD – 30TH FLOOR	1:100
2503373A–BD–308	E	DRAINAGE LAYOUT – TOWER 5 ROOF & UPPER ROOF FLOOR	1:100
2503373A–BD–401	D	DRAINAGE SYSTEM – INSTALLATION DETAILS (I)	N.T.S.
2503373A–BD–402	D	DRAINAGE SYSTEM – INSTALLATION DETAILS (II)	N.T.S.
2503373A–BD–403	D	DRAINAGE SYSTEM – INSTALLATION DETAILS (III)	N.T.S.



BLOCK PLAN
(SCALE: 1:1000)

PIPEWORK MATERIAL SCHEDULE

SYSTEM	DESCRIPTION			SIZE	MATERIAL
SOIL & WASTE / WASTE VENT PIPES	RESIDENTIAL TOWER	ABOVEGROUND	INSIDE RESIDENTIAL UNITS, SUNKEN AREA, EXTERNAL WALL & EXTERNAL STACK 1M ABOVE TRANSFER PLATE	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			PUBLIC AREA, INSIDE PIPE DUCT & TOWER 5 FLAT K & L 18/F SLAB BELOW 1.5M EXTERNAL AREA	BELOW 50mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
				50mm TO 150mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
				200mm TO 300mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
			PASSING THROUGH TRANSFER PLATE	ALL	EPOXY COATED CAST IRON PIPE TO BSEN 877
	PODIUM, CLUBHOUSE AREA AND CARPARK	ABOVEGROUND	INSIDE SUNKEN AREA (NOT CROSSING ANY FIRE COMPARTMENTATION / FLOOR SLAB)	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			PUBLIC AREA	BELOW 50mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
				50mm TO 150mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
				200mm TO 300mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
		UNDERGROUND		100mm & ABOVE	DUCTILE IRON TO B.S. EN 598
		UNDERGROUND	CONNECTION TO PUBLIC DRAINAGE SYSTEM (FOR BD's INFO)	100mm & ABOVE	POLYETHYLENE PIPE (PE100) TO BSEN12201
RAIN WATER PIPES	RESIDENTIAL TOWER	ABOVEGROUND	INSIDE RESIDENTIAL UNITS, SUNKEN AREA, EXTERNAL WALL & EXTERNAL STACK 1M ABOVE TRANSFER PLATE & 3/F FLAT BALCONY 1750MM ABOVE F.F.L INSIDE ALUMINUM CLADDING	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			PUBLIC AREA, INSIDE PIPE DUCT & TOWER 5 FLAT K & L 18/F SLAB BELOW 1.5M EXTERNAL AREA	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
				80mm TO 150mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
				200mm TO 300mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
			PASSING THROUGH TRANSFER PLATE	ALL	EPOXY COATED CAST IRON PIPE TO BSEN 877
	PODIUM AND CARPARK	ABOVEGROUND	SUNKEN AREA	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			PUBLIC AREA & INSIDE CAVITY WALL	BELOW 50mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
				50mm TO 150mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
				200mm TO 300mm	EPOXY COATED CAST IRON PIPE TO BSEN 877
				ABOVE 300mm	DUCTILE IRON TO B.S. EN 598
		UNDERGROUND		100mm & ABOVE	DUCTILE IRON TO B.S. EN 598
		UNDERGROUND	CONNECTION TO PUBLIC DRAINAGE SYSTEM (FOR BD's INFO)	100mm & ABOVE	PRECAST CONCRETE PIPE TO BS 5911 PART 100 CLASS H / POLYETHYLENE PIPE (PE100) TO BSEN12201
PUMPED DISCHARGE STORMWATER AND FOUL WATER PIPES				UP TO 65mm	DUCTILE IRON TO B.S. EN 598
				80mm AND ABOVE	DUCTILE IRON TO B.S. EN 598
A/C CONDENSATE DRAIN PIPES	RESIDENTIAL TOWER		EXTERNAL AND 1M ABOVE TRANSFER PLATE	BELOW 80mm	UPVC PIPE TO BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			INSIDE PIPE DUCT 1M ABOVE TRANSFER PLATE & EXTERNAL STACK 1M ABOVE TRANSFER PLATE & 3/F FLAT BALCONY 1750MM ABOVE F.F.L INSIDE ALUMINUM CLADDING	BELOW 80mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS EN 1329
				80mm TO 150mm	UPVC PIPE TO BS 4514 & BS EN 1329, INJECTED MOULDED PVC FITTINGS TO BS 4514 / BS EN 1329
			PASSING THROUGH TRANSFER PLATE	ALL	EPOXY COATED CAST IRON PIPE TO BSEN 877
SUB-SOIL DRAIN PIPE				ALL	PERFORATED CORRUGATED PLASTIC PIPES TO BS 4962

REMARK:
1. SHOULD THERE IS ANY DISCREPANCES BETWEEN THIS TABLE MENTIONED & THE TECHNICAL SPECIFICATION, THE REQUIREMENT IN THE TECHNICAL SPECIFICATION SHALL IN PREVAIL, SUBJECT TO ARCHITECT'S APPROVAL AND DISCRETION.
2. 15MM THICK ELASTOMERIC CLOSED CELL TUBE INSULATION TO BS 476 SHALL BE PROVIDED TO ALL A/C CONDENSATE DRAINS THAT RUN IN INDOOR AND AT ALL RAIN WATER PIPES RECEIVING A/C CONDENSATE WATER

MODIFICATIONS / EXEMPTIONS GRANTED AND AMENDMENT TO LOCATION (IF ANY) IN THE CURRENT SUBMISSION

DESCRIPTION		CONDITOINS	LOCATION WITH MODIFICATION/EXEMPTION GRANTED	DATE OF SUBMISSION	PERMIT NO.	KN4980(2023(MOD)			KN8(2025(MOD)				
					DATE OF GRANTED MODIFICATIONS	19/09/2023			07/01/2025				
					MONTH	08	03	11	03	06	11	04	08
					YEAR	23	24	24	25	25	25	26	26
					REV.	-	A	B	C	D	E	F	G
A	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS AND LATRINES) REGULATION 29 TO PERMIT THE PROVISION OF CLEANING ACCESS TO BE OTHER THAN CLEANING EYES;	(a) THE SAID WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE PLANS APPROVED ON 19 OCTOBER 2023 UNDER BD REF. NO. BD 4/4024/21. (b) REGARDING ITEMS (A), (B) & (C) ABOVE, SPECIFICATIONS OF THE EPOXY COATED CAST IRON PIPE AND ITS FITTING SHALL COMPLY WITH BS EN 877 OR OTHER EQUIVALENT STANDARD. (c) REGARDING ITEMS (D) ABOVE, SPECIFICATIONS OF THE DUCTILE IRON AND ITS FITTING SHALL COMPLY WITH BS EN 598 OR OTHER EQUIVALENT STANDARD. (d) THE CONDITIONS IMPOSED IN THIS PARAGRAPH ARE TO BE INCORPORATED IN THE SUBSEQUENT AMENDMENT PLANS FOR APPROVAL BEFORE THE FORM BA 13 IS SUBMITTED. (e) A CHECKLIST OF VALID FORMS BD 106 IS TO BE SUBMITTED AT THE TIME OF THE SUBMISSION OF FORM BA 13. (f) THIS PERMIT WILL EXPIRE ON 23 FEBRUARY 2025 IF CONSENT TO COMMENCE THE ABOVE WORKS IS NOT OBTAINED ON OR BEFORE THE SPECIFIED DATE OR WHERE SUCH CONSENT HAS BEEN OBTAINED BUT IS DEEMED TO BE REVOKED UNDER SECTION 20(1) OF THE BUILDINGS ORDINANCE AFTER THE SPECIFIED DATE.	FOR UNDERGROUND DRAINAGE PIPES		#	✓	✓	✓	✓	✓	✓	✓
B	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS AND LATRINES) REGULATION 44(4) TO PERMIT PROTECTION OF CAST IRON PIPES TO BE OTHER THAN ASPHALT COATING; AND		FOR ABOVEGROUND DRAINAGE PIPES		#	✓	✓	✓	✓	✓	✓	✓	✓
C	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS AND LATRINES) REGULATION 50(2) TO PERMIT JOINTING OF CAST IRON TO BE OTHER THAN LEAD CAULKING; AND		FOR ABOVEGROUND DRAINAGE PIPES		#	✓	✓	✓	✓	✓	✓	✓	✓
D	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS AND LATRINES) REGULATION 44(1) AND 54(1) TO PERMIT THE USE OF DUCTILE IRON PIPES FOR THE COVERED DRAINS AND COVERED SEWERS UNDER BUILDING;		FOR ABOVEGROUND DRAINAGE PIPES		#	✓	✓	✓	✓	✓	✓	✓	✓
1	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS & LATRINES) REGULATIONS 48: TO PERMIT THE DRAINS / SEWERS TO HAVE A FALL LESS THAN THAT SPECIFIED IN THE REGULATION; AND	(a) THE SAID WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE PLANS APPROVED ON 7 JANUARY 2025 UNDER BD REF. NO. 4/2024/21. (b) THE CONDITIONS IMPOSED IN THIS PARAGRAPH ARE TO BE INCORPORATED IN THE SUBSEQUENT AMENDMENT PLANS FOR APPROVAL BEFORE THE APPLICATION FOR AN OCCUPATION PERMIT IS SUBMITTED. (c) A CHECKLIST OF VALID FORMS BD 106 IS TO BE SUBMITTED AT THE TIME OF THE APPLICATION FOR AN OCCUPATION PERMIT. (d) REGARDING ITEM (1) ABOVE: CALCULATIONS DEMOSNTRATING THAT A MINIMUM FLOW VELOCITY OF 750MM PER SECOND IS ACHIEVED AND SUBMITTED TO THE SATISFACTION OF THE BUILDING AUTHORITY. (e) REGARDING ITEM (2) ABOVE:– NO CONDITION	FOR UNDERGROUND DRAINAGE PIPES					#	✓	✓	✓	✓
2	BUILDING (STANDARDS OF SANITARY FITMENTS, PLUMBING, DRAINAGE WORKS & LATERRINES) REGULATIONS 30(2)(B)(II): TO PERMIT THE ANTI-SYPHONAGE PIPE TO BE CONNECTED WITH THE BRANCH SOIL PIPE OR BRANCH WASTE PIPE AT A POINT NOT MORE THAN 750 MM FROM THE TRAP OUTLET.		FOR ABOVEGROUND DRAINAGE PIPES						#	✓	✓	✓	✓

LEGEND: # FIRST GRANTED ✓STILL APPLICABLE ✗ NOT APPLICABLE
Δ AMENDMENT TO THE LOCATION OF THE EXEMPTION/MODIFICATION PREVIOUSLY GRANTED. DEPENDING ON THE EXTENT OF THE AMENDMENT, NEW FORM BA16 AND BD106 MAY BE REQUIRED.

B.D. Ref.: BD 4/4024/21
BMI Ref.: -
F.S.D. Ref.: -
D.L.O. Ref.: -

| Rev. | Description | Drawn | Checked | Approved | Date |
|---

3/F +22.00
E/M ZONE
TRANSFER PLATE
+19.50
2/F +15.00
1/F 10.20
G/F +5.20
B1/F -1.00
B2/F -6.20
B3/F -9.60

(REFER TO 2503373A-BD-103 FOR CONTINUOUS)

ø100 VP TERMINATED AT 3000MM AFFL W/ WIRE BALLOON

+21.00 3300MM AFFL

REFER TO BS0(REFER TO 2503373A-BD-104 FOR CONTINUOUS)

M. CHANGING ROOM | ACC. TOILET | F. CHANGING ROOM | SPA 1 | SPA 2 | ACC. TOILET | LAV. | M. LAV. | F. LAV. | LANDSCAPE

FILTRATION PLANTROOM

+13.60 ø100 FD

FOUL WATER SUMP PIT FSP-2F-01 W/ SUMP PUMPS

SHOP 118 | SHOP 101 | F. LAV. | BABYCARE ROOM | M. LAV. | ACCESSIBLE TOILET | PAU RM. | SHOP 103 | SHOP 104 | SHOP 108

SHOP G12 | SHOP G11 | SHOP G21 | SHOP G19 | SHOP G22 | SHOP G05 | SHOP G06 | SHOP G03 | SHOP G04 | SHOP G16 | SHOP G15 | SHOP G01 | SHOP G14 | SHOP G13 | SHOP G02

ø100 VG

FMH-G-T02
TYPE T1_1
C.L. +5.80
I.L. +3.45
D.T.I.L. +3.30

TO PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH2) (UNDER SEPARATE SUBMISSION)
C.L. 5.56
I.L. 2.15

FMH-G-01
TYPE E1
C.L. +4.35
I.L. +2.87

FMH-G-T01
TYPE T1_1
C.L. +4.50
I.L. +2.80
D.T.I.L. +2.65

TO PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH1) (UNDER SEPARATE SUBMISSION)
C.L. 4.39
I.L. 2.50

CARPARK | MASTER METER RM. | W.M.C. | SMOKE EXTRACTION FAN RM. | SHOP B04 | SHOP B03 | PAU RM. (FOR RETAIL) | SHOP B03 | SHOP B02 | SHOP B04 | CARPARK | CARPARK | DRIVEWAY RAMP | SES PANEL ROOM | SUPERMARKET | REFUSE STORAGE AND MATERIAL RECOVERY CHAMBER 1 | WATER METER ROOM | AIR RELEASE FAN ROOM

PLEASE REFER TO DWG NO.: BS009-D0-003

PLEASE REFER TO DWG NO.: BS009-D0-003

TURN TABLE | CARPARK | CARPARK | CARPARK | CARPARK | CARPARK | CARPARK | F.S. & SPRINKLER WATER TANK AND PUMP RM. (FOR TOWER 1) | POTABLE WATER TANK & UPFEED PUMP RM. (FOR TOWER 1)

WSP-B2-04 | WSP-B2-03 | WSP-B2-02 | WSP-B2-01

WSP-B3-04
C.L. -9.60
B.L. -11.20
W/ SUMP PUMPS
WSP-B3-04-01 & 02
HEAD: 40M
FLOW: 3 L/S

WSP-B3-01
C.L. -9.60
B.L. -11.20
W/ SUMP PUMPS
WSP-B3-01-01 & 02
HEAD: 40M
FLOW: 3 L/S

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3ND BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
D	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

B.D. Ref.: BD 4/4024/21
BIM Ref.: -
F.S.D. Ref.: -
D.L.O. Ref.: -

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with all relevant and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in wholle or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR PODIUM (SHEET 1 OF 2)

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-101

Revision Number : F

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APUN 86165
21 September 2026

Received on
21 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



B.D. Ref. :	BD 4/402421
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3ND BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
D	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any
relevant drawings and other information issued for the job.
This drawing remains the copyright property of the Architect and is not
to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR PODIUM (SHEET 2 OF 2)

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-102

Revision Number : F

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APVAI 80/85
21 September 2026

Received on
21 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



TYPE T1



TYPE T2



TYPE T2.1



TYPE T3



TYPE T3.1



TYPE T4



TYPE T5



TYPE T6



TYPE T7



TYPE T8



TYPE T9

TYPE K1

TYPE K2

TYPE K3

TYPE K4

TYPE K5



TYPE T10

DRAINAGE SCHEMATIC FOR TOWER 1

350 DEPTH SUNKEN

400 DEPTH SUNKEN

225 DEPTH SUNKEN

NOTE:

1. Ø100 CROSS VENT PIPE WILL BE PROVIDED ON EVERY 3 FLOORS (6/F, 9/F, 12/F, 17/F, 20/F, 23/F, 27/F)
2. 4/F, 13/F, 14/F, 24/F NOT USE
3. NO DRAINAGE PIPE CONNECTION IS PERMITTED WITHIN A RESTRICTED ZONE AT EVERY OFFSET. THE RESTRICTED ZONE IS 1000MM ABOVE THE BEND AND WITHIN 2500MM AWAY FROM THE BEND HORIZONTALLY.

B.D. Ref. : BD 4/4024/21

BIM Ref. : -

F.S.D. Ref. : -

D.L.O. Ref. : -

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
D	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
The copyright of this drawing is vested in the Architect and it is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 1

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-103

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APUA | BORD
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



TYPE T1



TYPE T2



TYPE T2.1



TYPE T3



TYPE T3.1



TYPE T4



TYPE T5



TYPE T6



TYPE T7



TYPE T8



TYPE T9

TYPE K1

TYPE K2

TYPE K3

TYPE K4

TYPE K5

TYPE T10



DRAINAGE SCHEMATIC FOR TOWER 2

350 DEPTH SUNKEN

400 DEPTH SUNKEN

225 DEPTH SUNKEN

NOTE:

1. ø100 CROSS VENT PIPE WILL BE PROVIDED ON EVERY 3 FLOORS (6/F, 9/F, 12/F, 17/F, 20/F, 23/F, 27/F)
2. 4/F, 13/F, 14/F, 24/F NOT USE
3. NO DRAINAGE PIPE CONNECTION IS PERMITTED WITHIN A RESTRICTED ZONE AT EVERY OFFSET. THE RESTRICTED ZONE IS 1000MM ABOVE THE BEND AND WITHIN 2500MM AWAY FROM THE BEND HORIZONTALLY.

B.D. Ref. : BD 4/4024/21

BMM Ref. : -

F.S.D. Ref. : -

D.L.O. Ref. : -

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
D	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any
relevant drawings and other information issued for the job.
This drawing remains the copyright property of the Architect and is not
to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 2

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-104

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APVA (BOIS)
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



TYPE T1



TYPE T2



TYPE T2.1



TYPE T3



TYPE T3.1



TYPE T4



TYPE T5



TYPE T6



TYPE T7



TYPE T8



TYPE T9



TYPE K1

TYPE K2

TYPE K3



TYPE K4

TYPE K5

TYPE T10



DRAINAGE SCHEMATIC FOR TOWER 3

350 DEPTH SUNKEN

400 DEPTH SUNKEN

225 DEPTH SUNKEN

NOTE:

1. ø100 CROSS VENT PIPE WILL BE PROVIDED ON EVERY 3 FLOORS (6/F, 9/F, 12/F, 17/F, 20/F, 23/F, 27/F)
2. 4/F, 13/F, 14/F, 24/F NOT USE
3. NO DRAINAGE PIPE CONNECTION IS PERMITTED WITHIN A RESTRICTED ZONE AT EVERY OFFSET. THE RESTRICTED ZONE IS 1000MM ABOVE THE BEND AND WITHIN 2500MM AWAY FROM THE BEND HORIZONTALLY.

B.D. Ref.: BD 4/4024/21

BMM Ref.: -

F.S.D. Ref.: -

D.L.O. Ref.: -

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
D	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 3

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-105

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ho Man Andy
APVA 80/80
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



TYPE T1



TYPE T2



TYPE T2.1



TYPE T3



TYPE T3.1



TYPE T4



TYPE T5



TYPE T6



TYPE T7



TYPE T8



TYPE T9

TYPE K1

TYPE K2

TYPE K3

TYPE K4

TYPE K5

TYPE T10

DRAINAGE SCHEMATIC FOR TOWER 5

350 DEPTH SUNKEN

400 DEPTH SUNKEN

225 DEPTH SUNKEN

NOTE:

1. Ø100 CROSS VENT PIPE WILL BE PROVIDED ON EVERY 3 FLOORS (6/F, 9/F, 12/F, 17/F, 20/F, 23/F, 27/F)
2. 4/F, 13/F, 14/F, 24/F NOT USE
3. NO DRAINAGE PIPE CONNECTION IS PERMITTED WITHIN A RESTRICTED ZONE AT EVERY OFFSET. THE RESTRICTED ZONE IS 1000MM ABOVE THE BEND AND WITHIN 2500MM AWAY FROM THE BEND HORIZONTALLY.

B.D. Ref. : BD 4/4024/21

BMM Ref. : -

F.S.D. Ref. : -

D.L.O. Ref. : -

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
D	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
FOUL WATER SCHEMATIC DIAGRAM FOR TOWER 5

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-106

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APVAL BUILDS
17 September 2026

Received on 17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.


L TO R
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 VP FROM U/G TO H/L
ø150 WP AT H/L TO U/G
L TO R
ø100 RWP AT H/L TO U/G
ø100 VP(R) FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
L TO R
ø150 CPWP AT H/L TO U/G
ø100 PCPWP FROM U/G TO H/L
ø100 PCPWP FROM U/G TO H/L
WASTE WATER SUMP PIT
(RC UNDERGROUND)
WSP-B3-03
C.L. -8.10
B.L. -9.47
W/ SUMP PUMPS
WSP-B3-03-01 & 02
HEAD: 40M
FLOW: 3 L/S
WASTE WATER SUMP PIT
(RC UNDERGROUND)
WSP-B3-02
C.L. -8.10
B.L. -9.47
W/ SUMP PUMPS
WSP-B3-02-01 & 02
HEAD: 40M
FLOW: 3 L/S
RAIN WATER SUMP PIT
(RC UNDERGROUND)
RSP-B3-03
C.L. -8.10
B.L. -9.35
W/ SUMP PUMPS
RSP-B3-03-01 & 02
HEAD: 40M
FLOW: 10 L/S
RAIN WATER SUMP PIT
(RC UNDERGROUND)
RSP-B3-04
C.L. -8.10
B.L. -9.75
W/ SUMP PUMPS
WSP-B3-04-01 & 02
HEAD: 40M
FLOW: 10 L/S
T TO B
ø100 VP(R) FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
W/ ø150 CAP-OFF AT H/L FOR CDP
ø100 RWP F/A TO 150MM AFFL W/SHOE
225mm(W) DISH CHANNEL
ø80 WEEP HOLE (TYPICAL)
T TO B
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 VP(R) FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
RAIN WATER SUMP PIT
(RC UNDERGROUND)
RSP-B3-02
C.L. -8.64
B.L. -10.15
W/ SUMP PUMPS
RSP-B3-02-01 & 02
HEAD: 40M
FLOW: 10 L/S
T TO B
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 VP(R) FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
RAIN WATER SUMP PIT
(RC UNDERGROUND)
RSP-B3-01
C.L. -9.49
B.L. -10.75
W/ SUMP PUMPS
RSP-B3-01-01 & 02
HEAD: 40M
FLOW: 10 L/S
WASTE WATER SUMP PIT
(RC UNDERGROUND)
WSP-B3-04
C.L. -9.525
B.L. -11.15
W/ SUMP PUMPS
WSP-B3-04-01 & 02
HEAD: 40M
FLOW: 3 L/S
ø100 RWP F/A TO 150MM AFFL W/SHOE
WASTE WATER SUMP PIT
(RC UNDERGROUND)
WSP-B3-01
C.L. -9.525
B.L. -11.15
W/ SUMP PUMPS
WSP-B3-01-01 & 02
HEAD: 40M
FLOW: 3 L/S
L TO R
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 VP FROM U/G TO H/L
ø150 WP AT H/L TO U/G
L TO R
ø100 PCPWP FROM U/G TO H/L
ø100 PCPWP FROM U/G TO H/L
ø200 CPWP AT H/L TO U/G
RESIDENTIAL CARPARK
DRIVEWAY
EV CHARGER RM (FOR CARPARK)
SUMP PIT FOR VETROL INTERCEPTOR
LIFT PIT SUMP (-9.45)
LIFT PIT LEV. -10.20
-9.60
-9.52
-9.60
-9.52
-9.60
-9.52

LEGEND:

(W1) ø100 WP F/A TO H/L

(W2) ø150 WP F/A TO H/L

(R1) ø100 RWP F/A TO H/L

NOTES:

ALL SMOKE VENT ENCLOSURE TO BE -/240/240 FRR


L TO R
ø100 VP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø150 WP AT H/L TO U/G
L TO R
ø150 CPWP AT H/L TO U/G
ø100 PCPWP FROM U/G TO H/L
ø100 PCPWP FROM U/G TO H/L
L TO R
ø100 RWP AT H/L TO U/G
ø100 VP(R) FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø150 RWP F/A TO H/L
T TO B
ø150 WP F/A TO H/L
ø100 PCPWP AT H/L T/A
ø100 PCPWP AT H/L T/A
T TO B
ø100 VP(R) FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
W/ ø80 CAP-OFF AT H/L FOR CDP
L TO R
ø100 VP FROM SUMP PIT TO B3/F H/L
ø200 RWP FROM B3/F H/L TO SUMP PIT
2xø150 PRWP FROM SUMP PIT TO B3/F H/L
(REFER TO 2503373A-BD-202 FOR CONTINUOUS)
ø100 PWP AT H/L T/A
ø100 RWP F/A TO 150MM AFFL W/SHOE
L TO R
ø100 VP(R) AT H/L T/A
ø100 VP AT H/L T/A
ø100 PRWP AT H/L T/A
ø150 PRWP AT H/L T/A
ø150 PRWP AT H/L T/A
T TO B
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 VP(R) FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
T TO B
ø150 CPWP F/A TO H/L
ø100 PRWP AT H/L T/A
ø100 PWP AT H/L T/A
ø100 VP AT H/L T/A
T TO B
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 VP(R) FROM U/G TO H/L
ø100 RWP AT H/L TO U/G
ø100 RWP F/A TO 150MM AFFL W/SHOE
ø100 WP FROM B2/F TO B3/F H/L
(REFER TO 2503373A-BD-202 FOR CONTINUOUS)
2xø150 WP FROM B2/F U/G TO B3/F H/L
(REFER TO 2503373A-BD-202 FOR CONTINUOUS)
ø100 CPWP FROM B2/F U/G TO B3/F H/L
(REFER TO 2503373A-BD-202 FOR CONTINUOUS)
ø150 CPWP F/A TO H/L
L TO R
ø100 PCPWP FROM U/G TO H/L
ø100 PCPWP FROM U/G TO H/L
ø200 CPWP AT H/L TO U/G
L TO R
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 VP FROM U/G TO H/L
ø150 WP AT H/L TO U/G
RESIDENTIAL CARPARK
DRIVEWAY
CHARGER RM (MV CARPARK)
SUMP PIT FOR VENTIL BUILDING FLOOR
EV CHARGER RM (FOR VISITOR)
PRESSURIZATION STAIRCASE
LIFT PIT (FOR LIFT)
MANUAL UNLOADING
MASS CONCRETE FILL
FIRE HYDRANT AT H/L (HALF LANDING)
SMOKE VENT
CAPPING WALL
SAFETY WALL
EARTH BELL
DRY RISER INLET
SPRINKLER INLET
SPRINKLER TANK
SUMP PIT
LIFT PIT
EV CHARGER
M-EV CHARGER
FALL TO SUMP
FALL TO U/S
DRIVEWAY FALL TO U/S
SMOKE VENT VENT-1-P
SMOKE VENT VENT-2-P
SMOKE VENT VENT-3-P
SMOKE VENT VENT-4-P
SMOKE VENT VENT-5-P
SMOKE VENT VENT-6-P
SMOKE VENT VENT-7-P
SMOKE VENT VENT-8-P
SMOKE VENT VENT-9-P
SMOKE VENT VENT-10-P
SMOKE VENT VENT-11-P
SMOKE VENT VENT-12-P
SMOKE VENT VENT-13-P
SMOKE VENT

LEGEND:

- (W0) ø50 WP F/A TO H/L
- (W1) ø100 WP F/A TO H/L
- (W2) ø150 WP F/A TO H/L
- (R1) ø100 RWP F/A TO H/L
- (R2) ø150 RWP F/A TO H/L
- (S1) ø100 SWP F/A TO H/L
- (S2) ø50 SWP F/A TO H/L
- FRR ENCLOSURE (–/240/240)
- WEEP HOLE


WASTE WATER SUMP PIT (S.S. FLOOR STAND)
WSP–B2–04
C.L. –2.42
B.L. –4.02
W/ SUMP PUMPS
WSP–B2–04–01 & 02
HEAD: 20M
FLOW: 4.0 L/S
T TO B
ø100 WP AT H/L TO M/L
ø100 VP AT M/L TO H/L
ø100 PWP AT M/L TO H/L
ø100 PWP AT M/L TO H/L
ø100 RWP F/A TO 150MM AFFL W/ SHOE
ø150 WP AT H/L TO M/L
L TO R
ø150 RWP F/A TO H/L
ø100 WP F/A TO H/L
WASTE WATER SUMP PIT (S.S. FLOOR STAND)
WSP–B2–03
C.L. –4.75
B.L. –6.20
W/ SUMP PUMPS
WSP–B2–03–01 & 02
HEAD: 20M
FLOW: 4.5 L/S
L TO R
ø100 VP AT L/L TO H/L
2xø100 PWP AT L/L TO H/L
ø150 RWP AT H/L T/B
RAIN WATER SUMP PIT (RC SUSPENDED)
RSP–B2–02
C.L. –2.45
B.L. –8.00
W/ SUMP PUMPS
(REFER TO 2503373A–BD–201–2 FOR CONTINUOUS)
HEAD: 30M
FLOW: 38.0 L/S
ø100 VP FROM SUMP PIT TO B3/F H/L
(REFER TO 2503373A–BD–201–2 FOR CONTINUOUS)
L TO R
ø100 VP(R) F/B TO H/L
ø100 VP F/B TO H/L
ø100 PRWP F/B TO H/L
ø150 PRWP F/B TO H/L
ø150 PWP F/B TO H/L
2xø100 PRWP FROM SUMP PIT TO B3/F H/L
(REFER TO 2503373A–BD–201–2 FOR CONTINUOUS)
225mm(W) DISH CHANNEL
T TO B
ø100 WP F/A TO H/L
ø100 SWP F/A TO H/L
ø100 VP AT H/L T/A
225mm(W) DISH CHANNEL
T TO B
ø150 CPWP AT H/L T/B
ø100 PRWP F/B TO H/L
ø100 PWP F/B TO H/L
ø100 VP F/B TO H/L
ø150 CPWP AT H/L T/B
ø100 RWP F/A TO 150MM AFFL W/ SHOE
ø150 WP F/A TO M/L
ø100 WP F/A TO H/L
T TO B
ø100 WP F/A TO H/L
ø150 WP F/A TO M/L
ø100 RWP F/A TO 150MM AFFL W/ SHOE
ø150 WP F/A TO H/L
L TO R
ø100 PWP AT M/L TO H/L
ø100 PWP AT M/L TO H/L
ø100 VP AT M/L TO H/L
ø150 WP AT H/L TO L/L
WASTE WATER SUMP PIT (S.S. FLOOR STAND)
WSP–B2–02
C.L. –4.75
B.L. –6.20
W/ SUMP PUMPS
WSP–B2–02–01 & 02
HEAD: 20M
FLOW: 8.5 L/S
ø100 VP AT M/L TO H/L
ø150 PRWP AT H/L T/A
ø150 WP F/A TO H/L
L TO R
ø100 VP AT H/L T/A
ø100 VP(R) AT H/L T/A
ø100 PWP AT H/L T/A
ø100 RWP F/A TO 150MM AFFL W/ SHOE
ø100 RWP F/A TO H/L
L TO R
ø100 PRWP FROM U/G TO H/L
ø100 PRWP FROM U/G TO H/L
ø100 VP(R) FROM U/G TO H/L
ø150 RWP AT H/L TO U/G
W/ ø80 CAP–OFF AT H/L FOR CDP
L TO R
ø150 WP AT H/L TO U/G
ø100 PRWP FROM U/G TO H/L
ø100 VP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
225MM(W) SURFACE CHANNEL W/ GRATING COVER
ø100 RWP F/A TO L/L W/ SHOE
ø80 WP F/A TO H/L
ø100 WP F/A TO H/L
ø100 PCPWP AT H/L
& ENLARGED TO ø150 TO U/G
L TO R
ø100 VP AT H/L T/A
ø100 PRWP AT H/L T/A
ø150 WP F/A TO H/L
ø100 RWP F/A TO L/L W/ SHOE
L TO R
ø100 PWP FROM U/G TO H/L
ø100 PWP FROM U/G TO H/L
ø100 VP FROM U/G TO H/L
ø150 WP AT H/L TO U/G
T TO B
ø100 PWP AT H/L T/A
ø100 VP AT H/L T/A
ø150 RWP F/A TO 150MM AFFL W/ SHOE
T TO B
ø150 WP AT H/L T/B
ø100 PCPWP F/B TO M/L
ø100 PCPWP F/B TO H/L
T TO B
ø100 WP F/A TO H/L
ø100 PWP F/B T/A
ø100 RWP F/A T/B
ø100 WP F/A TO H/L
ø100 PSWP AT H/L T/A
ø150 PWP AT H/L T/A
ø150 BIGT
C.L. –1.244
I.L. –2.02
WASTE WATER SUMP PIT (S.S. FLOOR STAND)
WSP–B2–01
C.L. –4.75
B.L. –6.20
W/ SUMP PUMPS
WSP–B2–01–01 & 02
HEAD: 20M
FLOW: 7.0 L/S
L TO R
ø100 VP AT M/L TO H/L
ø100 PWP AT M/L TO H/L
ø100 PWP AT M/L TO H/L
ø100 VP AT M/L TO H/L
ø150 WP AT H/L TO L/L
ø100 WP F/A TO H/L
ø100 VP AT H/L T/A
L TO R
ø100 PRWP AT H/L T/A
ø100 VP AT H/L T/A
L TO R
ø100 WP F/A TO H/L
ø150 WP F/A TO H/L
ø80 RUNNING TRAP
ø80 WP F/A TO H/L
PUBLIC VEHICLE PARK (PVP)
COMMERCIAL CARPARK
DRIVEWAY
EV CHARGER RM. (FOR PVP)
ELEC. METER RM. (FOR PVP)
F.S. PUMP RM. (FOR TOWER 3)
54m³ SPRINKLER WATER TANK (FOR TOWER 3)
27m³ F.S. TANK WATER (FOR TOWER 3)
25.4m³ WATER TANK
25.4m³ WATER TANK
MOTOR CYCLE PARKING SPACE
T.B.E. RM. (FOR RESIDENTIAL)
T.B.E. RM. (FOR COMMERCIAL)
FLUSHING WATER TANK
54m³ SPRINKLER WATER TANK (FOR TOWER 1)
27m³ F.S. TANK WATER (FOR TOWER 1)
PUMP ROOM (FOR TOWER 1)
MASS CONCRETE
FLUSHING WATER TANK (FOR TOWER 2)
54m³ SPRINKLER WATER TANK (FOR TOWER 2)
PUMP ROOM (FOR TOWER 2)
TURN–TABLE
LOADING/UNLOADING BAY (7m x 3.5m x 4.1m HEADROOM) (FOR TOWER 3)
LOADING/UNLOADING BAY (7m x 3.5m x 4.1m HEADROOM) (FOR TOWER 2)
LOADING/UNLOADING BAY (7m x 3.5m x 4.1m HEADROOM) (FOR TOWER 1)

LEGEND:

- (K) ø40 WP AT L/L & ENLARGED TO ø50 T/B
- (W0) ø50 WP F/A TO H/L
- (W1) ø100 WP F/A TO H/L
- (R0) ø80 RWP F/A TO H/L
- (R1) ø100 RWP F/A TO H/L
- (R2) ø150 RWP F/A TO H/L
- (S1) ø100 SWP F/A TO H/L
- (S2) ø50 SWP F/A TO H/L
- (VP) ø50 SWP F/A TO H/L
- FRR ENCLOSURE (–/240/240)
- WEEP HOLE

T TO B
ø150 WP FROM H/L TO B/L
ø100 VP AT H/L T/A

L TO R
ø100 WP F/A TO H/L
ø200 SWP F/A TO H/L (T3)
ø200 SWP F/A TO H/L (T3)
ø150 SWP F/A TO H/L
ø100 CDP F/A TO H/L
ø150 RWP F/A TO H/L (T3)
ø200 RWP F/A TO H/L (T3 ROOF)
ø150 RWP F/A TO H/L (T3 ROOF)

PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH2) (UNDER SEPARATE SUBMISSION)
C.L. +5.39
A1 +2.16–450
A2 +2.635–300
X1 +2.14–450

TO PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH3) EXISTING FOUL WATER GOVERNMENT MANHOLE (FMH4025924) TO BE DEMOLISHED

ø400 STG (STG–R03)
C.L. +5.32
I.L. +2.77

SMH–G–T03
TYPE T2_1
C.L. +5.32
I.L. +2.69
D.T.I.L. +2.54
B.L. +1.645

PROPOSED NEW STORM WATER GOVERNMENT MANHOLE (SMH6) (UNDER SEPARATE SUBMISSION)
C.L. +4.99
A1 +2.362–600
X1 +2.18–600

FMH–G–T03
TYPE T1_1
C.L. +5.10
I.L. +3.24
D.T.I.L. +3.09

PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH4) (UNDER SEPARATE SUBMISSION)
C.L. +5.02
A1 +2.226–300
X1 +1.46–525

ø250 STG (STG–W03)
C.L. +5.10
I.L. +3.25

L TO R
ø100 VP(R) AT H/L T/A
ø100 PWP F/B TO H/L

ø250 STG (STG–W2)
C.L. +5.80
I.L. +4.73

ø100 VP(R) AT H/L T/A (FAI)
ø100 VP AT H/L T/A (FAI)

ø100 RWP AT H/L TO 150MM AFFL W/ SHOE

ø400 STG (STG–R01)
C.L. +5.80
I.L. +3.75

L TO R
ø100 VP F/B TO H/L
ø100 VP(R) F/B TO H/L
ø150 PRWP F/B TO H/L
ø150 WP FROM G/F SUNKEN TO B1/F H/L
(REFER TO BS009–D1–004 FOR CONTINUOUS)

SMH–G–T02
TYPE T2_1
C.L. +5.70
I.L. +3.15
DTIL +3.00

FMH–G–T02
TYPE T1_1
C.L. +5.80
I.L. +3.45
D.T.I.L. +3.30

L TO R
ø150 RWP AT H/L T/B
ø100 WP AT H/L T/B

L TO R
ø100 RWP FROM G/F SUNKEN TO B1/F H/L
ø100 KWP FROM G/F SUNKEN TO B1/F H/L
(REFER TO 2503373A–B0–204 FOR CONTINUOUS)

ø100 RWP FROM G/F SUNKEN TO B1/F H/L
(REFER TO BS009–D1–004 FOR CONTINUOUS)

ø100 RWP AT H/L TO SUNKEN

ø50 WP F/A & ENLARGED TO ø100 T/B

225mm(W) SURFACE CHANNEL W/ GRATING COVER (TYPE B)

L TO R
ø200 WP F/A TO H/L (T1&T2)
ø200 SWP F/A TO H/L (T1&T2)
ø100 VP AT H/L T/A

ø100 WP FROM G/F SUNKEN TO H/L

ø100 WP AT H/L T/B

T TO B
ø100 SWP F/A TO H/L
ø100 WP F/A TO H/L

REFER TO PART PLAN (A) FOR L/L DRAINAGE

FOUL WATER SUMP PIT (RC SUSPENDED)
FSP–B1–01
C.L. +0.20
B.L. –1.35
W/ SUMP PUMPS
FSP–B1–01–01 & 02
HEAD: 20M
FLOW: 3 L/S

ø80 VP F/B TO H/L

L TO R
ø100 WP F/A TO H/L
ø100 SWP F/A TO H/L

ø150 WP AT H/L T/B

T TO B
ø100 WP F/A TO H/L
ø100 RWP F/A TO H/L
ø100 WP F/A T/B

ø100 RWP AT H/L TO 150MM AFFL W/ SHOE

T TO B
ø100 WP AT H/L T/B
ø150 WP AT H/L T/B

ø100 WP AT H/L TO L/L

ø100 RWP AT H/L TO 150MM AFFL W/ SHOE

T TO B
ø150 RWP AT H/L T/B

ø400 STG (STG–R02)
C.L. +5.80
I.L. +3.75

ø400 RWP F/A TO H/L C/W RUNNING TRAP

225mm(W) COVERED CHANNEL

ø150 BIGT
C.L. –1.00
I.L. –2.02

225mm(W) SURFACE CHANNEL W/ GRATING COVER (TYPE C)

ø100 CDP F/A TO H/L

L TO R
ø150 RWP F/A TO H/L (T1&T2)
ø200 RWP F/A TO H/L (T1&T2 ROOF)

ø100 WP AT H/L T/B
ø100 VP H/L T/A

L TO R
ø100 PRWP F/B TO H/L
ø100 VP F/B TO H/L

L TO R
ø100 WP AT H/L T/B
ø150 WP AT H/L T/B

FMH–G–01
TYPE E1
C.L. +4.30
I.L. +2.87

PROPOSED NEW FOUL WATER GOVERNMENT MANHOLE (MH1) (UNDER SEPARATE SUBMISSION)
C.L. +4.39
A1 +2.58–300
X1 +2.50–450

FMH–G–T01
TYPE P1_1
C.L. +4.50
I.L. +2.80
D.T.I.L. +2.65

ø250 STG (STG–W01)
C.L. +4.30
I.L. +2.88

ø150 RWP AT H/L T/B

T TO B
ø100 PSWP F/B TO H/L
ø150 PWP F/B TO H/L

ø100 VP AT H/L T/A (FAI)

SMH–G–T01
TYPE T2_1
C.L. +5.20
I.L. +3.525
D.T.I.L. +3.375

PROPOSED MODIFIED STORM WATER GOVERNMENT MANHOLE (SMH2) (UNDER SEPARATE SUBMISSION)
C.L. +4.39
A1 +2.77–600
X1 +2.61–2x450

L TO R
ø100 CDP F/A TO H/L
ø150 KWP F/A TO H/L

ø400 RUNNING TRAP

L TO R
ø100 VP AT H/L T/A
ø100 WP F/A TO H/L
ø100 SWP F/A TO H/L (T5)

T TO B
ø150 RWP F/A TO H/L
ø100 CDP F/A TO H/L
ø150 RWP F/A TO H/L (T5 ROOF)

T TO B
ø100 VP(R) AT H/L T/A
ø100 VP AT H/L T/A
ø100 WP F/A TO H/L
ø100 SWP F/A TO H/L
ø200 SWP F/A TO H/L (T5)

T TO B
ø150 RWP F/A TO H/L (T5)
ø150 RWP F/A TO H/L (T5 ROOF)
ø150 RWP F/A TO H/L (2/F)
ø200 WP F/A TO H/L (T5)
T TO B
ø50 WP F/A TO H/L
ø50 WP F/A TO H/L

T TO B
ø100 VP AT H/L
ø150 RWP AT H/L
ø100 SWP AT H/L
ø250 RWP AT H/L
ø100 WP AT H/L
ø100 VP AT H/L

T TO B
ø100 PWP F/B TO H/L
ø100 VP F/B TO H/L

ø80 WEEP HOLE (TYPICAL)

L TO R
ø100 WEEP HOLE

ø100 VP AT H/L T/A (FAI)

ø100 WP AT H/L T/A

ø50 WP F/A & ENLARGED TO ø100 T/B

ø100 WP AT H/L T/B

L TO R
ø100 VP F/B TO H/L
ø100 PRWP F/B TO H/L

PROPOSED NEW STORM WATER GOVERNMENT MANHOLE (SMH4A) (UNDER SEPARATE SUBMISSION)
C.L. +4.63
A1 +2.97–600
X1 +2.42–600

PART PLAN FOR ST–B8 AT UPPER PART OF B1/F

PART PLAN FOR ST–B4 AT UPPER PART OF B1/F

PART PLAN FOR ST–B1 AT UPPER PART OF B1/F

PART PLAN FOR ST–B7 AT LEVEL 1.725

PART PLAN FOR ST–B3 AT UPPER PART OF B1/F

PART PLAN FOR ST–B11 AT UPPER PART OF B1/F

PART PLAN FOR ST–B2 AT LEVEL 2.075

BASEMENT 1 FLOOR PLAN



PART PLAN (A) – DRAINAGE LAYOUT PLAN FOR LAV. SUNKEN

B.D. Ref.:	BD 4/4024/21				
BIM Ref.:	-				
F.S.D. Ref.:	-				
D.L.O. Ref.:	-				

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3ND BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS
呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
The copyright of this drawing is vested in the Architect and it is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC–009)

Drawing Title :
DRAINAGE LAYOUT – BASEMENT 1 FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale 1:200 By A0

Drawing Number : 2503373A-BD-203

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APVA (BOIS)
21 September 2026

Received on
21 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND:

- (K0) ø50 WP F/A TO H/L
- (W0) ø50 WP F/A TO H/L
- (K1) ø100 KWP F/A TO H/L
- (W1) ø100 WP F/A TO H/L
- (R0) ø80 RWP F/A TO H/L
- (R1) ø100 RWP F/A TO H/L
- (S1) ø100 SWP F/A TO H/L
- (S0) ø50 SWP F/A TO H/L
- FRR ENCLOSURE (–/120/120)
- SUNKEN
- WEEP HOLE

LEGEND:

- (K) ø40 WP AT L/L & ENLARGED TO ø50 T/B
- (KS) ø40 WP AT L/L & ENLARGED TO ø50 TO SUNKEN
- (VP) ø50 ASP AT L/L TO H/L

N

BAILEY STREET
(25.82m WIDTH APPROX.)
(MEAN STREET LEVEL +4.650)

MA TAU WAI ROAD
(30.65m WIDTH APPROX.)

ADJOINING LOT

ADJOINING BUILDING

GROUND FLOOR PLAN
LEGEND (UNDER LEASE)

PART PLAN (A) – DRAINAGE LAYOUT PLAN FOR LAV. L/L

PART PLAN FOR ST-07 AT UPPER PART OF G/F

PART PLAN FOR ST-01 & ST-12 AT UPPER PART OF G/F

MANHOLE SCHEDULE (SOIL AND WASTE WATER)

MANHOLE NO.	MATCHING C.L.	CAST IRON C.L.	I.L.	D.T.I.L.	DEPTH(MM)	MANHOLE TYPE
FMH–G–01	N/A	4.30	2.87	–	1430	TYPE E1
FMH–G–T01	N/A	4.50	2.80	2.65	1850	TYPE T1_1
FMH–G–T02	N/A	5.80	3.45	3.30	2450	TYPE T1_1
FMH–G–T03	N/A	5.10	3.24	3.09	2010	TYPE T1_1

MANHOLE SCHEDULE (RAINWATER)

MANHOLE NO.	MATCHING C.L.	CAST IRON C.L.	I.L.	D.T.I.L.	DEPTH(MM)	MANHOLE TYPE
SMH–G–T01	N/A	5.20	3.525	3.375	1825	TYPE T2_1
SMH–G–T02	N/A	5.70	3.15	3.00	2700	TYPE T2_1
SMH–G–T03	N/A	5.32	2.69	2.54	2780	TYPE T2_1
SMH–G–02	N/A	5.20	4.20	–	1000	TYPE C1

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3ND BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

B.D. Ref.: BD 4/4024/21
BIM Ref.: -
F.S.D. Ref.: -
D.L.O. Ref.: -

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS
呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
All dimensions are in millimetres unless otherwise stated, and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - GROND FLOOR

Drawn By: CAD | Date: 08/26
Checked By: WWC | Date: 08/26
Approved By: DT | Date: 08/26
Project No.: | Issue Date: AUG 2026
File Path :
Scale: 1:200 By A0
Drawing Number: 2503373A-BD-204
Revision Number: E
Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ki Man Andy
APVA | BD/85
21 September 2026

Received on
21 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND:

- (K) ø40 WP AT L/L & ENLARGED TO ø50 T/B
- (W0) ø50 WP F/A TO H/L
- (K5) ø40 WP AT L/L & ENLARGED TO ø50 TO SUNKEN
- (W1) ø100 WP F/A TO H/L
- (R0) ø80 RWP F/A TO H/L
- (R1) ø100 RWP F/A TO H/L
- (R2) ø150 RWP F/A TO H/L
- (S1) ø100 SWP F/A TO H/L
- (S0) ø50 SWP F/A TO H/L
- (VP) ø50 VP AT L/L TO H/L
- FRR ENCLOSURE (-/120/120)
- SUNKEN

B.D. Ref. :	BD 4/4024/21
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
C	4TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

PART PLAN FOR ST-05 AT UPPER PART OF 1/F

PART PLAN FOR ST-06 AT UPPER PART OF 1/F

PART PLAN FOR ST-02 AT UPPER PART OF 1/F

1ST FLOOR PLAN

PART PLAN (A) – DRAINAGE LAYOUT PLAN FOR LAV. L/L

PART PLAN (B) – DRAINAGE LAYOUT PLAN FOR L/L / SUNKEN

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any other relevant drawings issued in connection with it.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - 1ST FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:200 By A0

Drawing Number : 2503373A-BD-205

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APVA1 BI/RS
21 September 2026

Received on 21 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND:

- (K) ø40 WP AT L/L & ENLARGED TO ø50 T/B
- (KS) ø40 WP AT L/L & ENLARGED TO ø50 TO SUNKEN
- (VP) ø50 ASP AT L/L TO H/L
- (V1) ø100 VP AT H/L T/A
- (VR) ø100 VP(R) AT H/L T/A
- (S1) ø100 SWP F/A TO H/L
- (S2) ø150 SWP F/A TO H/L
- (W0) ø50 WP F/A TO H/L
- (W1) ø100 WP F/A TO H/L
- (W2) ø150 WP F/A TO H/L
- (R) ø50 RWP F/A TO H/L
- (R0) ø80 RWP F/A TO H/L
- (R1) ø100 RWP F/A TO H/L
- (R2) ø150 RWP F/A TO H/L
- (CT) ø80 CDP F/A TO H/L
- FRR ENCLOSURE (–/120/120)
- SUNKEN
- WH



PART PLAN FOR ST-05
AT UPPER PART OF 2/F



PART PLAN FOR ST-06
AT LEVEL +17.424



PART PLAN FOR ST-06
AT UPPER PART OF 2/F



PART PLAN FOR ST-07
AT LEVEL +17.10



PART PLAN FOR ST-07
AT UPPER PART OF 2/F



PART PLAN FOR ST-08
AT UPPER PART OF 2/F


T TO B
ø200 SWP AT H/L
ø150 WP AT H/L
ø150 RWP AT H/L (T5 ROOF)
ø100 CDP AT H/L
ø100 RWP AT H/L
ø100 VP(R) AT H/L
ø100 VP(RETAIL) AT H/L
T TO B
ø200 SWP AT H/L
ø200 WP AT H/L
ø150 RWP AT H/L (T5 ROOF)
ø100 CDP AT H/L
ø100 RWP AT H/L
ø100 VP(R) AT H/L
ø100 VP(RETAIL) AT H/L
EXTENT OF FOOTBRIDGE
FOOTBRIDGE
T TO B
ø100 VP F/B TO H/L
ø80 PSWP F/B TO H/L
ø100 CDP AT H/L T/B
T TO B
ø150 RWP AT H/L (T3 ROOF)
ø100 CDP AT H/L
ø200 SWP AT H/L
ø100 RWP AT H/L
ø200 WP AT H/L
ø100 RWP FROM 1/F
T TO B
ø100 WP AT H/L
ø100 RWP AT H/L
ø50 CDP AT H/L
T TO B
ø200 RWP AT H/L (T3 ROOF)
ø100 CDP AT H/L
ø200 SWP AT H/L
ø100 RWP AT H/L
ø200 WP AT H/L
T TO B
ø200 RWP AT H/L (T3 ROOF)
ø100 CDP AT H/L
ø200 SWP AT H/L
ø100 RWP AT H/L
ø200 WP AT H/L
T TO B
ø200 RWP AT H/L (T3 ROOF)
ø100 CDP AT H/L
ø200 SWP AT H/L-T/B (T3)
ø150 RWP AT H/L T/B (T3 ROOF)
ø200 WP AT H/L T/B (T3)
T TO B
ø100 VP(R) F/B TO H/L
ø100 VP(RETAIL) F/B TO H/L
ø150 RWP AT H/L T/B (T3)
REFER TO PART PLAN (A) FOR L/L DRAINAGE
REFER TO PART PLAN (B) FOR L/L DRAINAGE
300mm(W) GUTTER AT H/L
ø100 VP(RETAIL) L/L TO H/L
L TO R
ø100 VP(RETAIL) F/B TO H/L
ø100 VP(R) F/B TO H/L
L TO R
ø150 RWP AT H/L T/B (T5)
ø150 RWP AT H/L T/B (T5 ROOF)
ø200 WP AT H/L T/B (T5)
L TO R
ø150 RWP AT H/L T/B (T5 ROOF)
ø100 CDP AT H/L T/B (T5)
ø100 WP AT H/L T/B (T5)
PLANTER
FOOTBRIDGE
ø100 RWP AT H/L T/B
ø100 RWP AT H/L TO L/L & DISCHARGED TO CHANNEL
REFER TO PART PLAN (C) FOR L/L DRAINAGE
ø100 VP AT H/L T/A
ø150 RWP AT H/L TO 150MM AFFL & DISCHARGED TO CHANNEL
ø100 RWP FROM 1/F TO H/L
ø100 RWP AT 1/F H/L
T TO B
ø100 WP AT H/L
ø100 RWP AT H/L
ø150 RWP AT H/L
ø100 CDP AT H/L
ø200 RWP AT H/L
ø200 SWP AT H/L
ø150 WP AT H/L
T TO B
ø200 RWP AT H/L (T2 ROOF)
ø200 SWP F/A TO H/L (T2)
ø200 WP F/A TO H/L (T2)
T TO B
ø100 RWP AT H/L T/B (T2)
ø150 RWP AT H/L T/B (T2)
ø100 CDP AT H/L T/B
ø150 RWP F/A TO H/L (T2 ROOF)
PART PLAN FOR ST-04
AT UPPER PART OF 2/F
L TO R
ø100 CDP AT H/L
ø100 WP AT H/L
ø150 WP AT H/L
ø100 SWP AT H/L
ø150 SWP AT H/L
ø100 SWP AT H/L
L TO R
ø100 VP(RETAIL) F/B TO H/L
ø200 WP AT H/L T/B (T2)
ø200 SWP AT H/L T/B (T2)
L TO R
ø100 VP(RETAIL) F/B TO H/L
ø100 VP(RETAIL) AT H/L T/A
ø50 VP AT L/L TO H/L
T TO B
ø200 SWP AT H/L
ø150 WP AT H/L
ø100 CDP AT H/L
T TO B
ø200 WP AT H/L
ø150 RWP AT H/L (T1 ROOF)
ø150 RWP AT H/L (T1)
ø100 CDP AT H/L
T TO B
ø200 WP AT H/L
ø200 SWP AT H/L (T1 ROOF)
ø200 RWP AT H/L (T1)
ø100 CDP AT H/L
T TO B
ø200 RWP AT H/L (T1 ROOF)
ø150 RWP AT H/L (T1)
ø100 CDP AT H/L
2ND FLOOR PLAN
PLAN FOR ST-02 & ST-03
PER PART OF 2/F
T TO B
ø32 WP AT L/L TO SUNKEN
ø50 WP AT L/L TO SUNKEN
T TO B
ø80 RWP AT 2/F SUNKEN TO 1/F H/L
ø80 WP AT 2/F SUNKEN TO 1/F H/L
ø100 SWP AT 2/F SUNKEN TO 1/F H/L
(REFER TO BS009-01-005 FOR CONTINUOUS)
ø50 WP AT 2/F SUNKEN TO 1/F H/L
ø32 WP AT L/L & ENLARGED ø50 TO SUNKEN
ø150 RWP AT 2/F SUNKEN TO 1/F H/L
ø150 RWP AT 2/F SUNKEN
ø80 RWP AT 2/F SUNKEN TO 1/F H/L
ø100 RWP AT 2/F SUNKEN TO 1/F H/L
(REFER TO BS009-01-005 FOR CONTINUOUS)
ø50 VP AT L/L TO H/L
ø50 PSWP AT L/L TO H/L
FOUL WATER SUMP PIT
W/ SUMP PUMPS
FSP-2F-01
550mm SUNKEN
650mm SUNKEN
700mm SUNKEN
750mm SUNKEN
300mm SUNKEN
400mm SUNKEN
600mm SUNKEN
800mm SUNKEN
850mm SUNKEN
1000mm SUNKEN
225mm(W) SURFACE CHANNEL W/ GRATING COVER (TYPE A)
LOUNGE 1
LOUNGE 2
LOUNGE 3
DANCE HALL
SITTING AREA 1
SITTING AREA 2
SITTING AREA 3
STUDY RM. 1
STUDY RM. 2
STUDY RM. 3
MUSIC ROOM
CHILDREN PLAY ROOM
POOL DECK
OUTDOOR SWIMMING POOL
JACUZZI
GYMNASIUM 1
GYMNASIUM 2
BALL COURT
FUNCTION RM. 1
FUNCTION RM. 2
FUNCTION RM. 3
MAINTENANCE CORRIDOR
2x4000L RC SURGE TANK
FILTRATION PLANT ROOM (FOR SWIMMING POOL)
LIFT CONTROL PANEL
LIFT VENT AT H/L
PLANTER WALL
METAL ROOF ABOVE
METAL CLADDING
STONE CLADDING
ARCH. FEATURE
TRANSFER PLATE ABOVE
BUILDING LINE ABOVE
TRELLIS ABOVE
WATER FEATURE
WATER WALL
RAISED FLOOR (FOR HOUSING REMOTE)
LV. SWITCH ROOM 1
LV. SWITCH ROOM 2
LV. SWITCH ROOM 3
LV. SWITCH ROOM 4
LV. SWITCH ROOM 5
LV. SWITCH ROOM 6
LV. SWITCH ROOM 7
LV. SWITCH ROOM 8
LV. SWITCH ROOM 9
LV. SWITCH ROOM 10
LV. SWITCH ROOM


WING KWONG STREET
FACING STREET
FACING STREET
FACING STREET
TOWER 3
TOWER 5
TOWER 2
TOWER 1
3/F DRAINAGE LAYOUT OF TOWER 3 , REFER TO DWG NO. 2503373A-BD-305
3/F DRAINAGE LAYOUT OF TOWER 5 , REFER TO DWG NO. 2503373A-BD-307
3/F DRAINAGE LAYOUT OF TOWER 1 & 2 , REFER TO DWG NO. 2503373A-BD-301
ADJOINING BUILDING
ADJOINING BUILDING
ADJOINING LOT
MA TAU WAI ROAD
WAN ON STREET
BAILEY STREET
TOP OF TRANSFER PLATE (COMMON) (ACCESS BY GONDOLA)
COMMON FLAT ROOF (ACCESS BY GONDOLA)
FLAT ROOF
PLANTER
ø100 VP F/B TO 3000MM AFF TERMINATED W/ WIRE BALLOON
ø100 RWP T/B
ø100 RWO
ROOF W/ ALUM. CLADDING (ACCESS BY GONDOLA)
METAL CANOPY (ACCESS BY GONDOLA)
TRELLIS
S.S. HATCH COVER
RC PARAPET WALL 900mm ht.
PORTAL FOR METAL GATE
ALIVE FEATURE
METAL RAILING
BUILDING LINE BELOW
CALCULATION OF PRESCRIBED WINDOW REFER TO DRAWING No. A1/GBP/U7
CALCULATION OF PRESCRIBED WINDOW REFER TO DRAWING No. A1/GBP/U17
14300
39900
17500
20875
18375
56675
22700
8750
25600
225.75
43200
7375
14650
36300
12500
6250
6425
6425
6425

LEGEND

- Ⓐ ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- Ⓑ ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- Ⓒ ø50 WP AT L/L T/B (FOR 3/F ONLY)
- Ⓓ ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- Ⓔ ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- Ⓕ ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC

T1-1G
225(W) DISH CHANNEL W/ FALL 1:100
225(W) SURFACE CHANNEL W/ FALL 1:100
T1-R
T TO B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L T/A
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
T TO B
ø80 RWP AT L/L T/B
ø80 RWP F/A TO L/L
L TO R
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 VP AT L/L T/A
T1-H
T1-1H
T1-1J
T1-10
ø65MM RWP AT SUNKEN & DISCHARGE TO SURFACE CHANNEL
225(W) SURFACE CHANNEL W/ FALL 1:100
T1-Q
X
TOP OF TRANSFER PLATE (COMMON)
T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
T1-AM
T1-P
Z
ø100 WP F/A T/B (PLANTROOM)
L TO R
ø80 CDP AT L/L T/B
ø80 CDP F/A TO L/L
ø150 RWP F/A T/B
T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP AT L/L T/B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L T/A
ø150 RWP F/A T/B
T1-AK
T1-N
Y
225(W) SURFACE CHANNEL W/ FALL 1:100
L TO R
ø150 WP AT H/L T/B (FOR H/Z 10/F TO 30/F)
ø100 WP AT H/L T/B (FOR L/Z 5/F TO 9/F)
ø100 SWP AT L/L T/B (FOR L/Z 5/F TO 9/F)
L TO R
ø80 RWP AT H/L T/B
ø80 RWP F/A TO H/L
T TO B
ø100 VP(RETAIL) F/B T/A
ø150 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L T/A
ø150 WP F/A TO L/L (FOR H/Z 10/F TO 30/F)
ø100 WP F/A TO L/L (FOR L/Z 5/F TO 9/F)
T1-AJ
T1-M
T TO B
ø80 CDP F/A TO H/L
ø80 RWP F/A TO H/L
225(W) SURFACE CHANNEL W/ FALL 1:100
ø65MM RWP AT SUNKEN & DISCHARGE TO SURFACE CHANNEL
225(W) SURFACE CHANNEL W/ FALL 1:100
L TO R
ø150 WP AT L/L T/B (FOR H/Z 10/F TO 30/F)
ø100 WP AT L/L T/B (FOR L/Z 5/F TO 9/F)
ø50 WP AT L/L T/B
L TO R
ø80 RWP AT H/L T/B
ø80 CDP AT H/L T/B
T1-AH
T1-K
L TO R
ø150 WP F/A TO L/L (FOR H/Z 10/F TO 30/F)
ø100 WP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø100 VP L/L T/A
ø100 WP F/A T/B (PLANTROOM)
T1-AG
T1-J
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
T TO B
ø100 WP F/A T/B
ø150 WP F/A TO H/L (FOR H/Z 10/F TO 30/F)
L TO R
ø100 SWP AT L/L T/B
ø100 VP AT L/L T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø65MM RWP AT SUNKEN & DISCHARGE TO SURFACE CHANNEL
225(W) SURFACE CHANNEL W/ FALL 1:100
T1-AF
T1-H
L TO R
ø150 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
T TO B
ø80 RWP F/A TO H/L
ø80 CDP F/A TO H/L
T TO B
ø80 CDP AT L/L T/B
ø80 CDP F/A TO L/L W/ 2 X ø32 TEE-OFF AT H/L
T1-AE
L TO R
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP L/L T/A
L TO R
ø80 RWP AT H/L T/B
ø80 RWP F/A TO H/L
T1-AD
225(W) SURFACE CHANNEL W/ FALL 1:100
L TO R
ø100 RWP AT L/L T/B
ø100 WP AT L/L T/B
L TO R
ø100 RWP F/A TO L/L
ø100 WP F/A TO L/L
L TO R
ø100 WP AT L/L T/B (FOR L/Z 5/F TO 9/F)
ø100 SWP AT L/L T/B (FOR L/Z 5/F TO 9/F)
ø150 SWP AT L/L T/B (FOR H/Z 10/F TO 30/F)
ø150 WP F/A T/B (PLANTROOM)
T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 WP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø100 VP L/L T/A
ø100 SWP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø150 SWP F/A TO L/L (FOR H/Z 10/F TO 30/F)
TOWER 1
TOWER 2
T TO B
ø80 RWP AT H/L T/B
ø80 RWP F/A TO H/L
L TO R
ø80 CDP F/A TO H/L W/ 2 X ø32 TEE-OFF AT H/L
ø80 CDP AT H/L T/B
T1-AC
T1-G
T1-F
T1-E
T1-D
T1-C
T1-B
T1-A
225(W) SURFACE CHANNEL W/ FALL 1:100
L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø150 RWP F/A T/B
ø100 VP AT L/L T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP AT L/L T/B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
T TO B
ø100 RWP AT L/L T/B
ø80 CDP AT L/L T/B
ø80 CDP F/A TO L/L W/ 2 X ø32 TEE-OFF AT H/L
ø100 WP F/A T/B
T TO B
ø80 RWP F/A TO L/L
ø80 CDP F/A TO L/L W/ 2 X ø32 TEE-OFF AT H/L
T1-AB
T TO B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L T/A
ø150 RWP AT L/L T/B
ø150 RWP F/A TO L/L
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
L TO R
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L F/A
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
L TO R
ø100 SWP AT L/L T/B
ø100 RWP F/A T/B
T1-AA
L TO R
ø80 CDP F/A TO L/L
ø80 CDP AT L/L T/B
L TO R
ø100 WP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø100 WP AT L/L T/B (FOR L/Z 5/F TO 9/F)
T1-C
L TO R
ø100 SWP F/A TO L/L (FOR L/Z 5/F TO 9/F)
ø100 SWP AT L/L T/B (FOR L/Z 5/F TO 9/F)
ø100 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 VP AT L/L T/A
T1-B
T1-A
T TO B
ø100 WP AT L/L T/B (FOR H/Z 10/F TO 30/F)
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F)
ø100 VP AT L/L T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F)
L TO R
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F)
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F)
ø40MM RWP AT L/L & DISCHARGE TO DISH CHANNEL
225(W) DISH CHANNEL W/ FALL 1:100
225(W) SURFACE CHANNEL W/ FALL 1:100
ø65MM RWP AT SUNKEN & DISCHARGE TO SURFACE CHANNEL
T1-1 T1-1A T1-1B T1-1C T1-1D T1-1E T1-1F T1-1G T1-1H T1-1J T1-10
T1-1 T1-2 T1-3 T1-4 T1-5 T1-6 T1-7 T1-8 T1-9 T1-10
G F
TOWER 1 TOWER 2
TOWER 1 LIFT LOBBY
TOP OF TRANSFER PLATE (COMMON)
3RD FLOOR PLAN – TOWER 1 & TOWER 2

B.D. Ref. :	BD 4/4024/21
BMI Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
D	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
Any discrepancies are to be immediately reported to the Architect, and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 1 & 2 3RD FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-301

Revision Number : F

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Ki Man Andy
APVA (BOR)
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE –/60/60
- DESIGNATED COMMON AREA UNDER DMC

T TO B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø50 ASP F/B TO L/L
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 VP F/B T/A

ø150 RWP F/A T/B

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø150 RWP F/A T/B

T TO B
ø100 VP(RETAIL) F/B T/A
ø150 SWP F/A TO L/L (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP F/A TO L/L (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø100 VP F/B T/A
ø150 WP F/A TO L/L (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A TO L/L (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

T TO B
ø50 ASP F/B TO L/L
ø50 ASP F/B TO L/L

T TO B
ø100 WP F/A TO H/L (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø50 ASP F/B TO L/L
ø100 VP F/B T/A

ø100 WP F/A T/B (PLANTROOM)

ø50 WP L/L T/B

ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 SWP L/L T/B
ø50 ASP F/B TO L/L

T TO B
ø50 ASP F/B TO L/L
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 WP F/A TO H/L (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B

L TO R
ø100 VP F/B T/A
ø150 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø50 ASP F/B TO L/L
ø50 ASP F/B TO L/L
ø100 VP F/B T/A

L TO R
ø150 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø50 ASP F/B TO L/L
ø100 VP F/B T/A

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø150 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 VP F/B T/A
ø50 ASP F/B TO L/L
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø80 CDP F/A T/B

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø150 WP F/A TO H/L (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø100 RWP F/A T/B
ø100 WP F/A T/B & UP AS ø100 VP

L TO R
ø50 ASP F/B TO L/L
ø50 ASP F/B TO L/L
ø150 WP F/A T/B (PLANTROOM)

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø50 ASP F/B TO L/L

ø100 WP F/A T/B (PLANTROOM)

ø100 RWP F/A T/B

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 VP F/B T/A
ø100 VP(RETAIL) F/B T/A

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø50 ASP F/B TO L/L
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

ø100 WP F/A T/B (PLANTROOM)

ø100 WP F/A T/B & UP AS ø100 VP

L TO R
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 SWP AT L/L T/B
ø50 ASP F/B TO L/L

ø100 RWP F/A T/B

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

ø100 RWP F/A T/B

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø50 ASP F/B TO L/L
ø100 WP F/A T/B & UP AS ø100 VP

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

ø50 ASP F/B TO L/L

ø100 WP F/A T/B (PLANTROOM)

ø100 RWP F/A T/B

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 VP F/B T/A
ø100 VP(RETAIL) F/B T/A

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø50 ASP F/B TO L/L
ø100 WP F/A T/B & UP AS ø100 VP

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

L TO R
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

ø100 WP F/A T/B (PLANTROOM)

ø100 RWP F/A T/B

T TO B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 SWP AT L/L T/B
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 RWP F/A T/B
ø150 WP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 VP F/B T/A
ø100 VP(RETAIL) F/B T/A

T TO B
ø100 SWP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 VP F/B T/A
ø150 SWP F/A T/B (FOR H/Z 10/F TO 30/F) & UP AS ø100 VP

T TO B
ø50 ASP F/B TO L/L
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

L TO R
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP
ø100 WP F/A T/B (FOR L/Z 5/F TO 9/F) & UP AS ø100 VP

5TH TO 30TH FLOOR PLAN – TOWER 1 & TOWER 2
(23–STOREYS)

B.D. Ref. :	BD 4/4024/21
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
D	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
All discrepancies between drawings, specifications and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 1 & 2 5TH - 29TH FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-302

Revision Number : F

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Ki Man Andy
APIA | BORS
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC



A — TYPICAL DETAIL OF ALUM. GRILLES FOR SCREENING OF EXTERNAL PIPES AT T2

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

B.D. Ref. : BD 4/4024/21

BIM Ref. : -

F.S.D. Ref. : -

D.L.O. Ref. : -

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be reported to the Architect.
This drawing is the intellectual property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 1 & TOWER 2 30TH FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-302-1

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APUN 86/85
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC



B.D. Ref.:	BD 4/4024/21
BIM Ref.:	-
F.S.D. Ref.:	-
D.L.O. Ref.:	-

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	5TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any
relevant drawings and other information issued for the contract.
This drawing remains the copyright property of the Architect and is not
to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 1 ROOF FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-303

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APUU 80/83
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE –/60/60
- DESIGNATED COMMON AREA UNDER DMC

B LIGHTNING POLE SECTION



TOP ROOF PLAN – TOWER 2

TOP ROOF PLAN – TOWER 1



UPPER ROOF PLAN – TOWER 1 & TOWER 2

B.D. Ref. :	BD 4/4024/21
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be reported to the Architect.
This drawing is the intellectual property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 1 &2 UPPER ROOF FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-304

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APUA | BD/BS
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC



B.D. Ref :	BD 4/4024/21
BIM Ref :	-
F.S.D. Ref :	-
D.L.O. Ref :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAY 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
D	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawing.
Refer to the architectural drawings and specifications for the description and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 3 3RD - 30TH FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.		Issue Date	AUG 2026
File Path :			
Scale	1:100	By	A0
Drawing Number :	2503373A-BD-305	Revision Number :	F

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APVA (WSB)
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- Ⓐ ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- Ⓑ ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- Ⓒ ø50 WP AT L/L T/B (FOR 3/F ONLY)
- Ⓓ ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- Ⓔ ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- Ⓕ ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC



TOP ROOF PLAN – TOWER 3



UPPER ROOF PLAN – TOWER 3



ROOF PLAN – TOWER 3

B.D. Ref. :	BD 4/4024/21				
BIM Ref. :	-				
F.S.D. Ref. :	-				
D.L.O. Ref. :	-				

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
E	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be reported to the Architect.
All rights reserved. This drawing is the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 3 ROOF & UPPER ROOF FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026
File Path :			
Scale	1:100	By	A0
Drawing Number :	2503373A-BD-306	Revision Number :	E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APIA | 80/85
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.

LEGEND

- Ⓐ ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- Ⓑ ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- Ⓒ ø50 WP AT L/L T/B (FOR 3/F ONLY)
- Ⓓ ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- Ⓔ ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- Ⓕ ø80 CDP F/A T/B W/ 2 X ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC



18th TO 30th FLOOR PLAN – TOWER 5
(12 STOREYS)



5th TO 17th FLOOR PLAN – TOWER 5
(11 STOREYS)



3RD FLOOR PLAN – TOWER 5

B.D. Ref. :	BD 4/4024/21				
BIM Ref. :	-				
F.S.D. Ref. :	-				
D.L.O. Ref. :	-				

Rev.	Description	Drawn	Checked	Approved	Date
-	BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	4TH BD SUBMISSION	CAD	WWC	DT	MAR 2025
C	5TH BD SUBMISSION	CAD	WWC	DT	JUN 2025
D	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
E	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
F	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
The drawing is the intellectual copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 5 3RD - 29TH FLOOR

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale			
	1:100	By	A0
Drawing Number :	2503373A-BR-307	Revision Number :	F

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Kit Man Andy
APOLIS/BSE
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



30TH FLOOR PLAN (H/L) – TOWER 5



TOP ROOF PLAN – TOWER 5



UPPER ROOF PLAN – TOWER 5



ROOF PLAN – TOWER 5

LEGEND

- (A) ø80 CDP F/A T/B W/ ø32 TEE-OFF AT H/L
- (B) ø80 RWP F/A T/B (TYPICAL FOR BALCONY)
- (C) ø50 WP AT L/L T/B (FOR 3/F ONLY)
- (D) ø100 SWP AT L/L T/B (FOR 3/F ONLY)
- (E) ø50 RWP AT L/L T/B (FOR 3/F ONLY)
- (F) ø80 CDP F/A T/B W/ 2 x ø32 TEE-OFF AT H/L (FOR 3/F ONLY)

- 50mm SUNKEN
- 225mm SUNKEN
- 300mm SUNKEN
- 350mm SUNKEN
- 400mm SUNKEN
- 450mm SUNKEN
- 525mm SUNKEN
- 575mm SUNKEN
- FRP ENCLOSURE -/60/60
- DESIGNATED COMMON AREA UNDER DMC

B.D. Ref. : BD 4/4024/21

BIM Ref. : -

F.S.D. Ref. : -

D.L.O. Ref. : -

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD 1	WWC	DT	AUG 2023
A	1(2ND BD SUBMISSION)	CAD 1	WWC	DT	MAR 2024
B	1(4TH BD SUBMISSION)	CAD 1	WWC	DT	MAR 2025
C	1(5TH BD SUBMISSION)	CAD 1	WWC	DT	NOV 2025
D	1(7TH BD SUBMISSION)	CAD 1	WWC	DT	APR 2026
E	1(8TH BD SUBMISSION)	CAD 1	WWC	DT	AUG 2026

TYPE II WORKS :
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all levels on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE LAYOUT - TOWER 5 30TH FLOOR, ROOF & UPPER ROOF LAYOUT PLAN

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale 1:100 By A0

Drawing Number : 2503373A-BD-308

Revision Number : E

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man, Andy
APUN 86/85
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-sheng
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



SCHEDULE FOR TRAPPED GULLY (UNLESS SPECIFIED)

DISCHARGE PIPE SIZE(mm)	RAINWATER DISPOSAL SYSTEM					
	L	W	D (min)	MH. CLEAR OPENING	GRATING SIZE	COVER SIZE
100 DIA.	500	500	300	300x300	450x450	450x450
150 DIA.	700	700	400	300x300	450x450	450x450
200 DIA. – 250 DIA.	900	900	600	450x450	600x600	600x600
300 DIA. – 400 DIA.	1200	1200	700	550x550	600x600	800x800

DISCHARGE PIPE SIZE(mm)	FOUL WATER DISPOSAL SYSTEM					
	L	W	D (min)	MH. CLEAR OPENING	GRATING SIZE	COVER SIZE
100 DIA.	300	300	300	150x150	200x200	300x300
150 DIA.	300	300	300	200x200	250x250	300x300
200 DIA. – 250 DIA.	400	400	400	300x300	450x450	450x450
300 DIA. – 400 DIA.	–	–	–	–	–	–

STG DESIGNATION	L	W	D	MH. CLEAR OPENING
STG–W1	750	750	1550	675x675
STG–W2	750	750	920	675x675
STG–W3	800	750	1830	675x675
STG–R2	1500	900	1190	675x675
STG–R3	1500	1200	2350	675x675

BACK INLET GULLY TRAP (B.I.G.T.) OR OPEN TRAPPED GULLY (O.T.G.)
NOT TO SCALE



MULTI-INLET OPEN TRAPPED GULLY/SEALED TRAPPED GULLY



DETAIL OF UNDERGROUND TRAPPED GULLY & GRATING



DETAIL OF RAIN WATER OUTLET (OPEN AREA)

B.D. Ref. :	BD 4/4024/21
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
–	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3RD BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026



UPVC PIPE PASSING THROUGH FIRE RATED WALL/SLAB WITH FIRE COLLAR



UPVC PIPE PASSING THROUGH FIRE RATED WALL/SLAB WITH FIRE WRAP



DETAIL OF FLOOR DRAIN



DETAIL OF RAIN WATER OUTLET - VERTICAL GRATING
(DETAIL OF WATER PROOFING, REFER TO ARCHITECT'S DETAILS)



SUMP PIT & SUBMERSIBLE PUMP SCHEDULE

SUMP PIT NO.	SUMP PUMP NO.	PUMP TYPE	COLUMN 1 ANTICIPATED DISCHARGE QUANTITY (L/S)	COLUMN 2 SELECTED SUMP PUMP (L/S)	COLUMN 3 SUMP PIT DIMENSION (M)		COLUMN 4 EFFECTIVE WATER DEPTH (M)	COLUMN 5 TOTAL DEPTH (M)	COLUMN 6 EFFECTIVE WATER VOLUME (M³)	COLUMN 7 TIME INTERVAL FOR START (MINUTES)	COLUMN 8 TIME INTERVAL FOR START (MINUTES)	COLUMN 9 NO. OF CYCLE FOR PUMP ON/OFF IN ONE HOUR	RESULT
					A	B	C						
FSP–1F–01	FSP–1F–01–01A02	FOUL WATER	2.5	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	21.6	2.8	ACCEPTABLE
FSP–2F–01	FSP–2F–01–01A02	FOUL WATER	2.5	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	21.6	2.8	ACCEPTABLE
FSP–3F–01	FSP–3F–01–01A02	FOUL WATER	2.5	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	21.6	2.8	ACCEPTABLE
WSP–B2–01	WSP–B2–01–01A02	WASTE WATER	6.3	7.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	14.3	4.2	ACCEPTABLE
WSP–B2–02	WSP–B2–02–01A02	WASTE WATER	7.9	8.5	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	16.1	3.7	ACCEPTABLE
WSP–B2–03	WSP–B2–03–01A02	WASTE WATER	3.9	4.5	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	17.3	3.5	ACCEPTABLE
WSP–B2–04	WSP–B2–04–01A02	WASTE WATER	3.1	4.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.35	540	12.9	4.7	ACCEPTABLE
WSP–B2–09	WSP–B2–09–01A02	WASTE WATER	1.5	2.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.05	540	24.0	2.5	ACCEPTABLE
WSP–B2–10	WSP–B2–10–01A02	WASTE WATER	7.0	8.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.55	540	10.3	5.8	ACCEPTABLE
WSP–B3–01	WSP–B3–01–01A02	WASTE WATER	2.0	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.55	540	13.5	4.4	ACCEPTABLE
WSP–B3–02	WSP–B3–02–01A02	WASTE WATER	2.0	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.27	540	13.5	4.4	ACCEPTABLE
WSP–B3–03	WSP–B3–03–01A02	WASTE WATER	2.0	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.27	540	13.5	4.4	ACCEPTABLE
WSP–B3–04	WSP–B3–04–01A02	WASTE WATER	2.0	3.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.55	540	13.5	4.4	ACCEPTABLE
RSP–B2–01	RSP–B2–01–01A02	RAINWATER	1.5	2.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.55	540	24.0	2.5	ACCEPTABLE
RSP–B2–02	RSP–B2–02–01A02	RAINWATER	36.3	38.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.50	1.85	1350	13.9	4.3	ACCEPTABLE
RSP–B3–01	RSP–B3–01–01A02	RAINWATER	9.0	10.0	(1 DUTY + 1STANDBY)		1.50	1.30	0.20	1.15	390	7.2	8.3	ACCEPTABLE
RSP–B3–02	RSP–B3–02–01A02	RAINWATER	9.0	10.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.60	540	10.0	6.0	ACCEPTABLE
RSP–B3–03	RSP–B3–03–01A02	RAINWATER	9.0	10.0	(1 DUTY + 1STANDBY)		1.50	1.30	0.20	1.15	390	7.2	8.3	ACCEPTABLE
RSP–B3–04	RSP–B3–04–01A02	RAINWATER	9.0	10.0	(1 DUTY + 1STANDBY)		1.80	1.50	0.20	1.55	540	10.0	6.0	ACCEPTABLE

*NOTE : = ON/OFF CYCLE SHALL BE LESS THAN 10 TIMES IN ONE HOUR. (FOR INFORMATION ONLY)

DESIGN CALCULATION FOR SUMP PITS (TYPICAL)
THE RESULTS ARE SUMMARIZED IN THE ABOVE TABLE
(A) THE WASTE DISCHARGE QUANTITY = COLUMN 1
SELECTED SUMP PUMP DUTY = COLUMN 2
(B) TECHNICAL DATA
(i) EFFECTIVE VOLUME OF SUMP PIT
= COLUMN 3 X COLUMN 4 X COLUMN 5
(ii) TIME INTERVAL FOR START (T)
T = (COLUMN 7 / COLUMN 1) + (COLUMN 2 / COLUMN 1)
= COLUMN 8
(iii) NOS. OF CYCLE FOR PUMP ON/OFF
= 60 / COLUMN 8
= COLUMN 9
(C) RESULT
(i) ON/OFF CYCLE ARE LESS THAN 10 TIMES IN ONE HOUR.
(ii) ACCEPTABLE.

DETAIL OF SUMP PIT
SIZE OF SUMP PIT REFER TO DRAINAGE PLANS
ALL LAPS SHALL BE TENSION LAP



DIMENSION LETTER	A	B	C	D	E	F	G	H	I	J
DIMENSIONS H	675	720	850	16	22	134	150	5	32	715
DIMENSIONS M	675	720	850	16	22	109	125	5	22	715

NOTES
H INDICATES HEAVY DUTY
M INDICATES MEDIUM DUTY

NOTE FOR COVER
FOR TERMINAL MANHOLE, ALL COVERS SHALL COMPLY TO DSD'S CURRENTLY ACCEPTABLE STANDARD (675mmx675mm HEAVY DUTY TYPE)

DETAIL OF MANHOLE COVER AND FRAME (DOUBLE SEAL)





GRATED COVER & FRAME



SERVICE PIPE SIZE 'Dp'	SIZE OF SLEEVE 'Ds'	SIZE OF GLAND 'Dg'
100	170	130
150	225	185
80	150	100
225	350	300
600	700	650
300	400	350

DETAIL OF PUDDLE SLEEVE THROUGH BASEMENT WALL

PIPE PASS THROUGH BASEMENT WALL



DETAIL OF C.I. COVER CHANNEL

TYPE	d
MEDIUM DUTY	25
HEAVY DUTY	50

THICKNESS OF GRATING

W	S	D	B
200	100	115	100
225	100	115	100
250	100	125	100
300	100	150	100
350	100	170	100
400	100	200	100
450	100	225	100

SURFACE CHANNEL SCHEDULE (FOR INFORMATION)



DETAIL OF DISH CHANNEL

W1	S1
200	100
225	100
250	100
300	100
350	100
400	100
450	100

DISH CHANNEL SCHEDULE
(NOTE: MAX. D1 DEPEND ON FALL)

DETAIL OF DISH CHANNEL

TYPE II WORKS :
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS

呂元祥建築師事務所

Check all measurements on site. Do not scale of drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE SYSTEM - INSTALLATION DETAIL (I)

Drawn By	CAD	Date	04/26
Checked By	WWC	Date	04/26
Approved By	DT	Date	04/26
Project No.	.	Issue Date	APR 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-401

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man, Andy
APVA1 80/85
27 April 2026

Received on
27 April 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
22 May 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



CAST IRON GRATING (MIN. 50MM THICK)



DETAIL OF PIPE HAUNCHING



BARE PIPE PASS THROUGH WALL



BARE PIPE PASS THROUGH SLAB



DETAIL OF PLANTER DRAIN



REMARK: 1) FLOOR DRAIN REFILLING PIPE CAN BE CONNECTED BELOW THE BASIN & KITCHEN SINK BOTTOM TRAP SUBJECT TO CONSULTANT'S APPROVAL AND DUE TO LIMITED INSTALLATION SPACE INSIDE THE CUPBOARD.

2) FLOOR DRAIN SHOWN IS INDICATIVE AND SHALL COMPLY WITH TECHNICAL SPECIFICATION AND REFER TO THE ACCEPTABLE MAKE LIST.

TYPICAL INSTALLATION DETAIL OF FLOOR DRAIN REFILLING PIPE CONNECTED FROM THE DRAINAGE PIPEWORK OF BASIN (ALTERNATIVE INSTALLATION METHOD)



PETROL INTERCEPTOR NO.	MATCHING C.I.	CAST IRON C.L.	I.L.	B.L.
PI-B3-01	N/A	−9.60	−10.2	−11.4

DETAIL OF PETROL INTERCEPTOR FOR CARPARK/CARPORT AREA
NOT TO SCALE



REMARK:
ALL REINFORCED CONCRETE UNITS
HAUNCHY FAMOTHER OF MANHOLES
MEHIDY BENCHY, LAID TO FALL, CHANS ,STEP IRON
MANHOLE COVER & GRATING, CHANNEL,,ETC

NOTES:
1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. PIPE DIAMETER : NOT EXCEEDING 450mm.
3. NORMAL RANGE OF DEPTH : 1750mm TO 4250mm, TO BE MEASURED FROM ROAD SURFACE TO LOWEST INVERT.
4. USED IN : STORMWATER DRAIN AND SEWER
5. JUNCTION : POSITION OF JUNCTION TO BE DETERMINED IN EACH INDIVIDUAL CASE. CHANNELS IMMEDIATELY UNDER ACCESS TO MANHOLE SHOULD BE AVOIDED.
6. FOUNDATION : FOUNDATION OF MANHOLE VARIES WITH SITE CONDITION. THEREFORE, IT SHOULD BE DETERMINED ON SITE BY THE ENGINEER.
7. CONCRETE MIX : GRADE 30/20
8. DIAMETER OF F.A.I. NORMALLY 100mm.

DETAIL OF TERMINAL MANHOLE T3_1
(NOT TO SCALE)



GREASE TRAP CAPACITY																	
GREASE INTERCEPTOR NO.					ADJ. AREA (m²)	ESTIMATED PEAK WATER CONSUMPTION (L/s)	PEAKING FACTOR	REQUIRED VOLUME (L)	TOTAL HOLDING CAPACITY (L)	PROVIDED VOLUME (L)	L1	L2	B	H	I	A
GT-B1-01	100				27.70	0.889	4.115	1167	3225	5400	1500	1500	1500	1200	min. 400	450
	125				1.35	0.158	5.500	190								
	150				43.50	1.256	3.325	1567								
	200				77.20	0.744	4.980	860								
	75				35.30	1.048	3.585	1238								
GT-B1-02	100	W.P.	0.074	19.30	0.794	4.115	959	1963	2423	7150	1100	1500	1100	min. 400	450	
	125			28.80	0.834	4.025	1051									
GT-B2-01	SUPERMARKET	W.P.	0.074	100	0.063	2.400	2500	2500	2662	7150	1100	1500	1100	min. 400	450	
GT-B2-02B	228	W.P.	0.074	28.50	0.889	4.025	1231	4438	4256	7150	1100	1500	1200	min. 400	450	
	219			28.10	0.889	4.095	1199									
	225			50.40	1.310	2.885	1513									
GT-B2-02A	267	W.P.	0.074	17.10	0.741	4.980	884	2544	4680	7150	1200	1500	1200	min. 400	450	
	216			36.00	1.156	3.750	1387									
	277			35.70	1.001	3.985	1268									
GT-B2-03	310	W.P.	0.074	7.10	0.339	5.500	407	4084	4704	7400	1400	1400	1400	1200	min. 400	450
	339			7.90	0.372	5.500	446									
	328			24.00	1.122	3.880	1346									
	892			45.90	1.374	3.335	1529									
	121			16.20	0.767	4.780	894									
GT-B2-04	803	W.P.	0.074	52.20	1.347	2.974	1616	3059	4704	7400	1400	1400	1400	1200	min. 400	450
	804			51.10	1.325	2.987	1595									
	325			8.60	0.411	5.500	460									

CANCELLED

TYPICAL DETAIL OF SS GREASE TRAP (FLOOR STAND)
NOT TO SCALE



NOTES :

ALL DIMENSIONS IN MILLIMETER

PIPE DIAMETER : (D) 150 TO 700mm

NORMAL RANGE OF DEPTH : 1500 TO 3000mm (MEASURED FROM ROAD LEVEL TO LOWEST INVERT)

USED IN : SEWER DRAIN AND STORMWATER

JUNCTION : POSITION OF JUNCTION TO BE DETERMINED IN EACH INDIVIDUAL CASE.CHANNELS IMMEDIATELY UNDER ACCESS TO MANHOLE SHOULD BE AVOIDED

– ALL REINFORCEMENT DETAILS SHALL BE PROVIDED BY STRUCTURAL ENGINEER

TYPICAL DETAIL OF STANDARD MANHOLE (TYPE E)
NOT TO SCALE



DETAIL OF PLANTER DRAIN (ABOVE GROUND)
NOT TO SCALE



DETAIL OF PLANTER DRAIN W/ TRAP (UNDERGROUND)
NOT TO SCALE



CONNECTION BETWEEN DRAINAGE STACK AND MAIN ANTI-SYPHONAGE PIPE
NOT TO SCALE



INSTALLATION METHOD / CLEANING DETAIL OF EPOXY COATED CAST IRON PIPE
NOT TO SCALE

B.D. Ref. :	BD 4/4024/21
BIM Ref. :	-
F.S.D. Ref. :	-
D.L.O. Ref. :	-

Rev.	Description	Drawn	Checked	Approved	Date
-	1BD SUBMISSION	CAD	WWC	DT	AUG 2023
A	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
B	3RD BD SUBMISSION	CAD	WWC	DT	NOV 2024
C	4TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
D	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS
呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
This drawing is to be read in conjunction with the specification and any discrepancies are to be immediately reported to the Architect.
The copyright of this drawing is reserved by the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE SYSTEM - INSTALLATION DETAIL (II)

Drawn By	CAD	Date	04/26
Checked By	WWC	Date	04/26
Approved By	DT	Date	04/26
Project No.	-	Issue Date	APR 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-402

Revision Number : D

Drawing Purpose

Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APPLI 80/80
22 May 2026

Received on
22 May 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
22 May 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.



MANHOLE COVER OPENING SIZE (mm)	450	675
X (mm)	600 (min)	825 (min)
Y (mm)	(DIA. +500)	(DIA. +500) OR 675, WHICHEVER IS GREATER

NOTES:
ALL DIMENSIONS IN MILLIMETER
PIPE DIAMETER(A) : 100 TO 450
NORMAL RANGE OF DEPTH(D) : 2500mm MAX. (MEASURED FROM ROAD LEVEL TO LOWEST INVERT)
USED IN JUNCTION : STORMWATER DRAIN AND SEWAGE
: POSITION OF JUNCTION TO BE DETERMINED IMMEDIATELY UNDER ACCESS TO MANHOLE IN EACH INDIVIDUAL CASE. CHANNELS SHOULD BE AVOIDED.
DIAMETER OF F.A.I. : NORMALLY 100mm

NOTES:
1) ALL DIMENSIONS ARE IN MILLIMETERS.
2) PIPE DIAMETER : EQUAL OR GREATER THAN 450mm
3) NORMAL RANGE OF DEPTH : 1750 TO 4250mm AS SPECIFIED (MEASURED FROM ROAD LEVEL TO LOWEST INVERT)
4) USED IN : STORMWATER DRAIN OR SEWER
5) JUNCTION : POSITION OF JUNCTION TO BE DETERMINED IN EACH INDIVIDUAL CASE CHANNELS IMMEDIATELY UNDER ACCESS TO MANHOLE SHOULD BE AVOIDED (FOR INFORMATION ONLY)
6) FOUNDATION : FOUNDATION OF MANHOLE VARIES WITH SITE CONDITION. THEREFORE, IT SHOULD BE DETERMINED ON SITE BY THE ENGINEER. (FOR INFORMATION ONLY)
7) CONCRETE MIX : GRADE 30/20 (FOR INFORMATION ONLY)
8) DIAMETER OF F. A. I. NORMALLY 100mm.
- ALL REINFORCEMENT DETAILS SHALL BE PROVIDED BY STRUCTURAL ENGINEER







W.C. W/ P-TRAP
A+B ≤ 750MM
CASE "A"
TOWER 2: M.BATH : FLAT A
TOWER 5: BATH : FLAT A, M

W.C. W/ P-TRAP
A+B ≤ 750MM
CASE "B"
TOWER 1: LAV. : FLAT A
TOWER 1: BATH : FLAT A, B, E, M
TOWER 2: BATH : FLAT A, C, D, G
TOWER 3: M.BATH : FLAT A

W.C. W/ S-TRAP
A+B ≤ 750MM
CASE "A"
TOWER 1: M.BATH : FLAT A, B, M
TOWER 1: BATH : FLAT C, D, F, G, H, J, K, L
TOWER 2: BATH : FLAT B, E, F, H, K, L, M, N, P
TOWER 3: M.BATH : FLAT B
TOWER 3: BATH : FLAT A, B, C, F, G, H, J, K, L, Q, R
TOWER 5: BATH : FLAT B, C, D, E, F, G, K, L

W.C. W/ S-TRAP
A+B ≤ 750MM
CASE "B"
TOWER 2 : FLAT J, Q
TOWER 3 : FLAT D, E, M, N, P
TOWER 5 : FLAT H, J

DETAIL OF TERMINAL MANHOLE T1_1
(NOT TO SCALE)

DETAIL OF TERMINAL MANHOLE T2_1
(NOT TO SCALE)

TYPICAL DETAILS FOR A.S.P. CONNECTION FOR W.C. IN SUNKEN
NOT TO SCALE





DETAIL OF REFILLING PIPE CONNECTION
(NOT TO SCALE)





DETAIL OF MATCHING COVER W/ PAVING BLOCK FINISHES FOR MANHOLE
(NOT TO SCALE)



PLAN OF DOUBLE SEALED MATCHING COVER W/. FINISHES FOR MANHOLE
(NOT TO SCALE)



DETAIL OF MATCHING COVER (TYPE A)
(NOT TO SCALE)



DETAIL OF MATCHING COVER (TYPE B)
(NOT TO SCALE)



U-CHANNEL VEHICULAR CAST IRON (TYPE C)
(NOT TO SCALE)



DETAIL OF MATCHING COVER (TYPE D)
(NOT TO SCALE)



DETAIL OF CONDENSATE
DRAIN PIPE CONNECTION
(NOT TO SCALE)

Rev.	Description	Drawn	Checked	Approved	Date
-	2ND BD SUBMISSION	CAD	WWC	DT	MAR 2024
A	3RD BD SUBMISSION	CAD	WWC	DT	NOV 2024
B	6TH BD SUBMISSION	CAD	WWC	DT	NOV 2025
C	7TH BD SUBMISSION	CAD	WWC	DT	APR 2026
D	8TH BD SUBMISSION	CAD	WWC	DT	AUG 2026

B.D. Ref. : BD 4/4024/21
BIM Ref. : -
F.S.D. Ref. : -
D.L.O. Ref. : -

TYPE II WORKS
THE WORKS SHOWN ON THESE PLANS ARE TYPE II WORKS DRAINAGE IN RESPECT OF WHICH CONSENT IS APPLIED FOR THE PURPOSE OF FAST TRACK CONSENT APPLICATION UNDER REGULATION 33 OF THE BUILDING (ADMINISTRATION) REGULATIONS.

RONALD LU & PARTNERS
呂元祥建築師事務所

Check all measurements on site. Do not scale off drawings.
Report any discrepancies between the drawings and site and any discrepancies are to be immediately reported to the Architect.
This drawing remains the copyright property of the Architect and is not to be reproduced in whole or in part without permission of the Architect.

Project Title :
PROPOSED DEVELOPMENT AT BAILEY STREET & WING KWONG STREET, TO KWA WAN, KOWLOON INLAND LOT NO. 11279 (URA PROJECT KC-009)

Drawing Title :
DRAINAGE SYSTEM - INSTALLATION DETAIL (III)

Drawn By	CAD	Date	08/26
Checked By	WWC	Date	08/26
Approved By	DT	Date	08/26
Project No.	-	Issue Date	AUG 2026

File Path :

Scale N.T.S. By A0

Drawing Number : 2503373A-BD-403

Revision Number : D

Drawing Purpose
Buildings Department
Amended Plan

Digitally signed by LEUNG Ka Man Andy
APUAL 86/85
17 September 2026

Received on
17 September 2026

Plan Approved
(Digitally Signed)
IP Yiu-shing
Building Surveyor
for BUILDING AUTHORITY
21 September 2026

Note: This plan has been processed on a curtailed check basis under the centralized processing system as promulgated in PNAP ADM-19. The duties of the authorized person, registered structural engineer and/or registered geotechnical engineer concerned as specified under section 4(3)(b) and the provision of section 14(2)(c) of the Buildings Ordinance are of particular relevance in this regard.